Government of Tender Notice

Invitation of Tender Notice Nos.9,10 & 11 /Seri/Engg/Civil/PCR/BIR/2018-'19.

Sealed Tenders are invited by the Executive Engineer, Directorate of Textiles (Sericulture), West Bengal 45. Ganesh Chandra Avenue(2nd floor), Kolkata - 13 for the following works in the district of Birbhum under P.C.R. from the bonafide experienced and resourceful contractors having experience in such types of works in pure Govt. Department/Zilla Parishad.

and the same	ment/Zilla Parishad.	The state of the s	A CONTRACTOR OF THE PROPERTY O		
NIT No.	Name of the Work	Estimated Cost	Earnest Money	Place of Work	Time of completion
09	Repairing and replacement work of Sub-merssible Pump Motor set with accessories at Kalitha Sericulture Complex, Birbhum under P.C.R.	Rs.99,354/- (Rupees ninety nine thousand three hundred fifty four) only.	Rs.2,485/- (Rupees two thousand four hundred eighty five)only.	Kalitha Sericulture Complex, Birbhum.	1(oné) month from the date of issue of Work Order.
10*	Electrical wiring for Office Building of the Dy.Director of Textiles(Sericulture), Suri, Birbhum under P.C.R.	Rs.1,18,421/- (Rupees one lakh eighteen thousand four hundred twenty one) only.	Rs.2,965/- (Rupees two thousand nine hundred sixty five) only.	O/o. the Deputy Director, Textiles (Sericulture) Gol Market, Suri, Birbhum.	-do-
11.	Electrification works for Re-structuring at Grainage Building (1st floor),(internal wiring and allied works) at Kotasur Sericulture Complex, Kotasur, Birbhum.	Rs.3,03,053./- (Rupees three lakh three thousand fifty three) only.	Rs.7,580/- (Rupees seven thousand five hundred eighty)only.	Kotasur Sericulture Complex, Kotasur, Birbhum.	

Tender papers (NIT, Priced Schedule & Form: 2911(ii) etc. may be obtained/down loaded from *seriwbgov.org* at free of cost. Tender papers should be submitted in the box kept at Head Quarters, Kolkata & papers should be arranged in the following manner.

j	Last date and time of submission of Tender	23.08.2018	upto 3-00 P.M. at Head Quarters, Kolkata.
	Date and time of opening of Tender	23.08.2018	upto 3-30 P.M. at Head Quarters, Kolkata.

The Technical Bid will be opened at first. The financial Bid will be opened only if the Technical Bid is found acceptable. Labour Cess will be deducted from Bill value as per Govt. Rules. All the original copies are to be shown for verification. The details may be seen in the Office of the Commissioner of Textiles (Sericulture), Govt. of West Bengal, 45, Ganesh Chandra Avenue(2nd floor), Kolkata - 13 on any working days and in the Website's seriwbgov.org. The Commissioner of Textiles (Sericulture), Govt. of West Bengal reserves the right to reject/accept all the applications without showing any reasons thereof. It any date as above happens to be holiday the next working day will be considered as stipulated date. Acceptance of lowest tender is not obligatory. N.S.C./K.V.P. will not be accepted as Earnest Money. Only the Bank Draft of a Nationalized Bank will be considered as earnest money. Acceptance of lowest Tender is not obligatory. Notwithstanding anything contained in this Notice Inviting Tender, the other terms & conditions and special terms & conditions will remain binding upon all concerned.

Executive Engineer,
Directorate of Textiles (Sericulture),
West Bengal

Price schedule for the Restructuring of Grainage Buildings (1st floor) (Internal wiring and allied work) at Kotasur Sericulture Comp. Unit under R.K.V.Y.

SI.	. Description of Item	Unit	Rate	QTY.	Appendix
1.0	Farthling the whole in till in		1.000	X11	Amount
	Earthling the whole installation 2" dia loft Pipe (ISI Medium) and as per P.W.D. Schedule. [PWD 2017/ Page-G-1/ Sl no. 2(a)].	Set	1369.00	8.00	10952.00
2.0	Distribution wiring in 1.1.KV grade 2x22/0.3 (1.5sq.mm) Single Core Standard "FR" PVC insulated & unsheathed Copper wire (Approve make) in 20mm, Rigid conduit FR(Precision make) with 1.1 grade 1x22/0.3 (1.5Sqmm) for ECC incl. necy Fittings to light/gan/Ex Fan point with modular type switch fixing on modular Sheet Steel (16SWG) Switch board Cum JB on wall complete with 2Nos Suitable Size PH & N copper bar with perplex top cover 3mm, thick including 175mm. x 100mm, x 65mm, inspection box making earthling attachment as to G.S. (6mtr. Average long) [PWD 2017/ Page-E-24/ Sl no. 3(a)].	No.	801.00	65.00	52065.00
3.0	Wiring in 1.1KV grade. 2x36/0.3(2.25 Sq.mm) Single core standard "FR" insulated & unsheathed single core standard copper wire (Approved make) with 1.1kV grade 1x36/0.3(2.5 Sq.mm) Single Core Standard Copper wire (Approved make) in 20mm size rigid conduit FR (Precision) including necessary fitting for mainline. [PWD 2017/ Page-E-14/ Sl.no. 1(a)].	Mtr	127.50	200.00	25500.00
4.0	S/F 250V 5.A plano key type plug socket with switch (Anchor) without top in existing switch board including connection & as per PWD Schedule. [PWD 2017/ Page-E-24/ Si no. 1(b)].	No.	216.00	ď	864.00
<i>J</i> 6	S/F 250V 15A flush type plug socket with 15A piano key pipe switch (Anchor) on sheet metal box with backlit top cover and earthling attachment including sheet metal box with backlit top cover as per PWD Schedule. (PWD 2017/ Page-E-6/Sl no. 17(b)].	No.	201.00	4	804.00
6.0	Supply & Fixing 240 V. 25A Modular type socket, 25 A, Modular type starter (Brand approved by EIC) with 25A Modular switch type DF MCB (C-Curve) and 6 Module GI Modular type switch board with 6 Module top cover plate flushed in wall incl. S&F switch board and cover plate and making necy, connections with PVC Cu wire and earth continuity wire etc. [PWD 2017/ Page-E-19/SI no. 18].	No.	1047.00	3	3141.00
7.0	Supplying & Fixing Industrial Plug & Socket board with 240 V, 20A, SPN & Earth Metal industrial Plug socket & 20A Industrial top incl.	No.	904.00	9	8136.00

	S&F 20 A SP MCB breaking capacity 10kA (C- Curve) in SS enclosure fixed on wall and necessary connection. [PWD 2017/ Page-D-12/ Sl no. 17].				
8.0	S/F Socket type Fan regulator (Step Type) & as per instruction OFFICE. [PWD 2017/ Page-E-6/ Sl no. 18(a)].	No.	236.00	6	1416.00
9.0	S/F CFL lamp 18Wt. (Philips make). (rate analysis attached).	No.	253.00	6	1518.00
10.0	Wiring 1.1 KV grade 2x56/0.3(4sqmm) Single core standard "FR" insulated & unsheathed single core standard copper wire (Approved make) with 1.1 KV grade 1x36/0.3(2.5 sq.mm) Single Core Standard Copper wire (Approved make) in 20mm size rigid conduit FR(Precision) including necessary fitting from MCB distribution Board to power plug & A/C Point. [PWD 2017/ Page-E-11/ Sl no. 1(e)].	Mtr	132.00	140	18480.00
11.0	S/F 12" dia Exhaust Fan Crompton Greaves make (EXHD-323-4-1) Single Ph including connection as required into shutter & lourer and making hole on wall and mending good damage to wall & as per PWD Schedule. (rate analysis attached).	No.	4979.74	4	19918.96
12.0	S/F outdoor type New generation energy saving & environmental friendly long life versatile pressure dia cast aluminum IP65 road way luminaire with high power LED as light source (Cat No LHEWEBP 7PL6S025) Havel's make with lamp type 25W LED 5000K Havel's make (rate analysis attached).	No.	3507.45	5	17537.25
13.0	S/F Mirolta slim batten 36W Hf with suitable for single TMS 520/136 lamp with reflector. (rate analysis attached).	No.	843.00	40	33720.00
14.0	S/F 48" regular Ceiling Fan Crompton Greaves Make (Entrust 50-5Star) & as per PWD approved. (rate analysis attached).	No.	2213.00	5	11065.00
15.0	4 Way (4+12) Double Door MCB distribution board Havel's make (Cat Bi-DCD PTHO DRWO4) with 1No 63A TPN Usikatir, 12Nos 6-32A SP MCB Havel's make on iron angle frame on wall. [PWD 2017/ Page-D 6/6, 7/7 & 11/14].	Set	5701.00	1	5701.00
16.0	S/F SP&N 8 way single Door MCB distribution board CRABTREE make (Cat No-DCDKSHODCW08) with 1no 20Amps DP MCB & 6nos 6A SP MCB CRABTREE make on iron angle frame on wall for Office bldg. [PWD 2017/ Page-D-10 & D-6/7].		2960.00	1	2960.00
17.0	S & Laying 4 Core 16sq.mm PVC Cable partly in underground trench 460mm. Wide x 760mm average depth with brick protection on the top of the cable with 8Nos bricks per meter including filling the space between the bricks & Cable and also the trench with sifted soil as per PWD Schedule. (rate analysis attached).		315.00	92	28980.00
18.0	S/F 20A 2Way MCB DB Box with metal enclosure. [PWD 2017/ Page-D-6/ Sl no.7 & D-9/Sl no. 11].	No.	438.00	1	438.00
19.0	S/F 32mm dia protection pipe as per as PWD Schedule. [PWD 2017/Page-F-6/Sl no. 11(b)].	Mtr	218.00	6	1308.00

20.0	S/Laying 3.5 Core 50Sq.mm PVC/A (Aluminum) Cable in the underground trench as per PWD Schedule from WBSEB to Pilar Box.	Mtr	472.58	17	8033-86
	(rate analysis attached).	u			
21.0	Supplying and fixing compression type gland complete with brass gland, brass ring & rubber ring for dust & moisture-proof entry of XLPE/PVC armoured cables as below:	to device reference, and so commission who are to commission of the commission of th			2 9
21.01	3.5 Core 50Sq.mm PVC/A (Aluminum) Cable. [PWD 2017/ Page-F-4/Sl no. 7(d)].	No	197.00	6	1182.00
21.02	4 Core 16sq.mm PVC Cable. [PWD 2017/ Page-F-4/Sl no. 7(c)].	No	132.00	12	1584.00
	Finishing the end of following XLPE/PVC armoured cables by crimping method incl. supplying and fixing solder less socket (Dowels make), tapes, anticorrosive paste & jointing materials for following cables:-				2 ·
	3 ^{1/2} core 50 sq.mm PVC/A cable. [PWD 2017/ Page-F-5/Sl no. 5(b-XVI)].	Set	209.00	6	1254.00
	4 core 16 sq. mm PVC cable. [PWD 2017/ Page-F-5/Sl no. 5(b-XII)].	Set	95.00	12	1140.00
	Add : District Charge @ 5 % -				257698·07 (+) 12884·90
	Add: G.S.T. @ 12%				270582.97
	TOTAL Rs.				303052.92
	SAY RS.				303053/

SAY RUPEES THREE LAKHS THREETHOUSAND FIFTY THREE ONLY

Executive Engineer
Directorate of Texhilas (Sericulture
Government of West Bengal