

Government Tender Notice

Invitation of Tender Notice No. 33,34,35,37,38,39 /Seri/Engg/civil/PCR/BIR/2019-'20.

Sealed Tenders are invited by the Executive Engineer, Directorate of Sericulture, West Bengal, 45, Ganesh Chandra Avenue, (2nd floor), Kolkata-13 for the following works under P.C.R. in the district of Birbhum from the bonafide experienced and resourceful contractors having experienced in such type of works in pure Govt. Department/Zilla Parishad.

N.I.T No.	Name of the Work	Estimated Cost	Earnest Money	Place of Work.	Time of completion of work.
33.	Construction of grill gate at unit-II complex and repairing of submersible pump with allied works (Qtr's. Pump) at Kotasur Sericulture Complex, Birbhum Under P.C.R.	Rs.1,38,090/-	Rs.3,460/-	Kotasur Sericulture Complex, Birbhum	1(one month) from the date of issue of Work Order.
34.	Repairing and renovation of E.O. Qtr. (converted into office of the Joint Director of Sericulture, West Zone) at Sriniketan Sericulture composit unit Bolpur, Birbhum under P.C.R.	Rs.4,96,391/-	Rs.12,410/-	Sriniketan Sericulture composit unit Bolpur, Birbhum	1(one month) from the date of issue of Work Order.
35.	Sanitary & plumbing works with compound fencing around the proposed office of the Joint Director of Sericulture, West Zone at E.O. Qtr. at Sriniketan Sericulture composit unit, Bolpur, Birbhum under P.C.R.	Rs.4,93,553/-	Rs.12,340/-	Sriniketan Sericulture composit unit Bolpur, Birbhum	1(one month) from the date of issue of Work Order
37.	Lowering of existing submersible pump motor set at Bolpur Sericulture composit unit, Muluk farm, Birbhum under P.C.R.	Rs.1,99,56/- 19,750/-	Rs.500/-	Bolpur Sericulture composit unit, Muluk farm, Birbhum	15(fifteen) days from the date of issue of Work Order
38.	Sanitary & plumbing works, painting etc. with allied works of office building at Sriniketan Sericulture composit unit Bolpur, Birbhum	Rs.4,50,368/-	Rs.12,260/-	Sriniketan Sericulture composit unit Bolpur, Birbhum	1(one month) from the date of issue of Work Order
39.	Repairing of boundary wall (Broken portion) at Bolpur Sericulture composit unit, Muluk farm, Birbhum under P.C.R.	Rs.4,58,843/-	Rs.11,475/-	Bolpur Sericulture composit unit, Muluk farm, Birbhum	1(one month) from the date of issue of Work Order

Tender papers (NIT), Priced Schedule & Form-2911(ii) etc. may be obtained/downloaded from seriwb.gov.org at free of cost. Tender should be submitted/dropped in the box kept at Head Quarters, Kolkata and papers should be arranged in the following manner.

Last date & time of submission of Tender	20.06.2019 upto 3-00 P.M. at Head Quarters, Kolkata.
Date & time of opening of Tender	20.06.2019 at 3-30 P.M. at Head Quarters, Kolkata.

Envelop - I should be superscribed as Technical Bid for N.I.T No.....SL No. of Work, Name of agency and it should contain (Self Attested) PAN Card. Last I.T. Return, valid GSTIN Registration, P.Tax Challan, Credential (similar nature of work at about 60% of Tender Value), EMD and sealed.


Envelop - II, should be super scribed as Financial Bid for N.I.T. No..... SL No. of Work, Name of Agency and should contain filled in - **2911 (ii)** quoting the Rate and Sealed.

2(two) envelopes as noted above (I & II) should be put in a bigger envelop and sealed. Agency should write clearly N.I.T. No., Name of Work, SL.No. and Name of Agency on this Envelope and drop the same as per schedule mentioned in this N.I.T.

Technical Bid will be opened first. Financial Bid will be opened only if the technical Bid is found acceptable.

Labour cess will be deducted from bill value as per Govt. Rules. All original copies are to be shown for verification. The details may be seen in the Office of the **Directorate of Textiles(Sericulture), West Bengal**, 45, Ganesh Ch, Avenue (2nd floor),Kolkata-13 on any working days and web site seriwb.gov.org. The **Commissioner of Textiles (Sericulture), West Bengal** reserves the right to reject/cancel all the applications without showing any reasons thereof. If any date as above happens to be holidays the next working days will be considered as stipulated date. Acceptance of lowest tender is not obligatory.

N.S.C./K.V.P. will not be accepted as Earnest Money. Only the Bank Draft of a Nationalised Bank will be considered as Earnest money. Notwithstanding anytime contained in this Notice Inviting Tender, the other termconditions and special terms & conditions will remain binding upon all concerned.



Executive Engineer,
Directorate of Textiles (Sericulture),
West Bengal

Dated, 29/5/2019.

Memo.No. 155(3)/ENG/SERI/PCR/BIR/8 (Vol.-6),

Copy forwarded for information & necessary action to :-

1. The Deputy Director of Textiles (Sericulture), Suri , Birbhum.
2. The Notice Board of this Directorate, Headquarters, Kolkata.
3. The Website of this Directorate of Textiles (Sericulture), West Bengal.


Executive Engineer,
Directorate of Textiles (Sericulture),
West Bengal.

Priced schedule for repairing and renovation of E.O. Qtr. Converted into Joint Director of Sericulture office, at Sriniketan comp. Unit, Bolpur, Birbhum under P.C.R.

Sl	Description of item	Quantity	Unit	Rate	Amount
1.00	Dismantling all types of plain cement concrete works, stacking serviceable materials at site and removing rubbish as directed within a lead of 75m.a) Upto 150 thick.	10.00	Cum	939.00	9390.00
2.00	Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. (a) Depth of excavation not exceeding 1,500 mm.	24.00	Cum	119.27	2862.00
3.00	Single brick flat soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with powdered earth or local sand.	20.00	Sqm.	264.00	5280.00
4.00	Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes.(i) Pakur Variety.	3.50	Cum	4684.63	16396.00
5.00	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes.(i) Pakur Variety	4.50	Cum	5289.63	23803.00
6.00	Hire and labour charges for shuttering with centring and necessary staging upto 4 m. using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams, columns, lintels curved or straight including fitting, fixing and striking out after completion of works. (upto roof of ground floor) a) 25 mm. to 30 mm. thick wooden shuttering as per decision & direction of Engineer-in-charge.	31.00	Sqm	328.00	10496.00

7.	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc. initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every inter-section, complete as per drawing and direction. For works in foundation, basement and upto roof of ground floor / upto 4m. Tor steel/Mild steel.	0.45	M.T.	55,629.00	25,033.00
8.	Brick work with 1st class bricks in cement mortar (6:1) In foundation and plinth	1.35	Cum	4480.00	6048.00
9.	Filling in foundation or plinth by silver sand in layers not exceeding 150 mm. as directed and consolidating same by thorough saturation with water ramming complete, including the cost of supply of sand.	11.00	Cum	487.41	5362.00
10.	125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor.	14.00	SQ.m	588.00	7812.00
11.	Artificial stone in floor, dado, staircase etc. with cement concrete (1:2:4) with stone chips, laid in panels as directed with topping made with ordinary or white cement (as necessary) and marble dust in proportion (1:2) including smooth finishing and rounding off corners and including application of cement slurry before flooring works, using cement @ 1.75 kg./sq.m. all complete including all materials and labour. 35 mm. thick.	33.00	Sq.m	296.00	9768.00
12.	Stripping off worn out plaster and raking out joints of walls, celings etc. Upto any height and in any floor including removing rubbish within a lead of 75m as directed.	393.00	Sqm	19.00	7467.00
13.	Supplying, fitting & fixing UPVC pipes A-Type and fittings conforming to IS: 13592-1992 with all necessary clamps nails including making holes in walls, floors etc. Cutting trenches in any soil, through masonry concrete structure etc. If necessary and mending good damages including jointing with jointing materials (Spun yarn, valamoid / bitumen / M. Seal etc.) complete. UPVC Pipes: 110 mm. Dia	7.20	M	251.00	1807.00
14.	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course scaffolding/staging where necessary (ground floor). [Excluding cost of chipping over concrete surface] With 1:6 cement mortar 20 mm. Thick plasters.	208.00	Sqm	170.00	35360.00
14.1	15 mm. Thick plaster	157.00	Sqm	149.00	23393.00
14.2	With 4:1 cement mortar, 10 mm. Thick plaster.	67.00	Sqm	121.00	8107.00
15.	Neat cement punning about 1.5 mm. Thick in wall, dado, window, sills, floor, drain etc.	155.00	Sqm	34.00	5270.00

16.	25 mm thick Tiles as per IS: 1237-2012 for foot path, ramp, staircase of public building(over 25 m m thick (Avg) Cement mortar (1:3) & Cement Slurry @ 4.4 kg/Sq. M at back side of Block. Cement for Mortar & Slurry to be supplied by Department).	7.00	Sqm	863.00	6041.00
17.	Supplying and laying true to line and level vitrified tiles of approved brand (size not less than 600 mm X 600 mm X 10 mm thick) in floor, skirting etc. set in 20 mm sand cement mortar (1:4) and 2 mm thick cement slurry back side of tiles using cement @ 2.91Kg./sqM or using polymerised adhesive (6 mm thick layer applied directly over finished artificial stone loor/Mosaic etc without any backing course) laid after application slurry using 1.75 Kg of cement per sqM below mortar only, joints grouted with admixture of white cement and colouring pigment to match with colour of tiles / epoxy grout materials of approved make as directed and removal of wax coating of top surface of tiles with warm water and polishing the tiles using soft and dry cloth upto mirror finish complete including the cost of materials, labour and all other incidental charges complete true to the manufacturer's specification and direction of Engineer-in-Charge. (White cement, synthetic adhesive and grout material to be supplied by the contractor) (T) With application slurry @ 1.75 kg/Sq.m, 20 mm sand cement mortar (1:4) & 2 mm thick cement slurry at back side of tiles, 0.2 kg/ Sq.m white cement for joint filling with pigment. (A) Light Colour.	84.00	Sqm	1676.00	140784.00
18.	Supplying, fitting & fixing 1st quality Ceramic tiles in walls and floors to match with the existing work & 4 nos. of key stones (10mm) fixed with araldite at the back of each tile & finishing the joints with white cement mixed with colouring oxide if required to match the colour of tiles including roughening of concrete surface, if necessary or by synthetic adhesive & grout materials etc. (A) Floor With Sand Cement Mortar (1:4) 20 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91Kg/Sq.m & joint filling using white cement slurry @ 0.20kg/Sq.m. (a) Area of each tile above 0.09 Sq.m (i) Coloured decorative	7.00	Sqm	891.00	6237.00
18.1	B) Wall With Sand Cement Mortar (1:3) 15 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg/Sq.m & joint filling using white cement slurry @ 0.20kg/Sq.m. (a) Area of each tile above 0.09 Sq.m (i) Coloured decorative	30.00	Sqm	1089.00	32670.00

19.	<p>Supplying fitting and fixing in position approved P.V.C. door frame (Matt finish) made of extruded P.V.C. multichamber hollow section having dimensions 60mm x 50mm x 2mm (+/- 0.2mm), horizontal section will be joined with vertical section by galvanized steel screws after inserting two number steel brackets as reinforcement making suitable space for placing hinges, one steel tube 40mm x 20mm x 1.20 mm will be inserted on one full vertical side of the frame (hinge side) as reinforcement, the frame will then be fixed in the opening with the help of P.V.C. expandable astener/wooden gutties and galvanized steel screws including cost of all materials and labour, hire charges of tools and appliances, carriage of all materials, taxes and all other incidental charges complete.</p>	10.00	M	445.00	4450.00
20.	<p>Supplying fitting and fixing P.V.C. door shutter of approved quality & shade in position, the style & rail of the P.V.C. door shutter will be made of rigid P.V.C. multicavity hollow chamber of 59 mm x30 mm section with 2.0 mm (+/-0.2 mm) wall thickness. Horizontal & vertical section shall be fixed to each other by self tapping screws and 1 solid polymeric or M.S. galvanized tubular 'L' shaped bracket 100mm x 200mm Labour for taking out door and window frame including shutter for repair or replacement of different parts of the frame & refixing the same including mending good all damages complete. (Concrete and brick work for mending damage will be paid separately)Upto area 2.5 Sq.m in each corner of the shutter frame for placing hinges. Polymer based multicavity hollow section of 120 mm x30mm with 2.0 mm (+/- 0.2 mm) wall thickness will be fitted in the middle, reinforced by solid polymer bar of 200 mm long at both ends and screws from both sides as lock rail. The section frame will then be fitted in by PVC panels of size 100 mmx25mm with wall thickness of 1.2 mm (+/- 0.2 mm) and 2 nos. of 6 mm dia bright rod will be inserted horizontally with both side check and nut system and stretches where fixing of hinges / hasp bolt / tower bolt / door ring are required to be strong enough to with stand wear and tear. The rate is inclusive of cost of all materials, labour, and hire of tools and plants and appliances/c carriage of all materials taxes and all other incidental charges complete.</p>	2.90	Sqm	2278.00	6606.00
21.	<p>Supplying, fitting and fixing windows and ventilators with or without integrated grills conforming to IS 1038-1975 and manufactured from rolled steel sections conforming to IS 7452-1974 with non-friction projecting type, box type hinges, glazing clips, lugs locking bracket, handle plate etc, including hoisting in position, straightening if required, fixing lugs in cement concrete (1:2:4) with stone chips 20 mm down cutting holes and mending good</p>	1.10	Sqm	1663.00	1829.00

	damages to match with existing surface complete in all respect excluding glazing. (b) Openable steel windows as per IS sizes with side hung shutters and horizontal glazing bars. [The extra rate admissible for the openable portion only]				
22.	Supplying, fitting and fixing in position fibre glass panes of approved quality with resin, nail, clip etc. as per IS:12866-1989. (In all floors for internal wall & upto 6 m height for external wall. 4 mm sheet.(6.72 K.G. per Sq,m	4.35	Sqm	1719.00	7478.00
23.	Labour for taking out door and window frame including shutter for repair or replacement of different parts of the frame & refixing the same including mending good all damages complete. (Concrete and brick work for mending damage will be paid separately) Upto area 2.5 Sq.m	34.80	Sqm	119.00	4141.00
24.	Wood work in door and window frame fitted and fixed in position complete including a protective coat of painting at the contact surface of the frame excluding cost of concrete, Iron Butt Hinges and M.S clamps. (The quantum should be corrected upto three decimals). (e) Sal : Malaysian	0.34	Cum	75572.00	25694.00


TOTAL=Rs.439284.00

Add G.S.T. @12% (+) = Rs. 52,714.00

(C.G.S.T 6%+S.G.S.T6%) TOTAL=Rs. 4, 91,998.00

Add Labour welfare cess @ 1%(+) =Rs. 4,393.00

TOTAL=Rs.4, 96,391.00


Executive Engineer
Directorate of Textiles (Sericulture)
Government of West Bengal