

Government Tender Notice

Invitation of Tender Notice No.58 & 59 /Seri/Eng/Civil/RKVY/MLD/2019-'20.

Sealed Tenders are invited by the Executive Engineer, Sericulture, West Bengal, 45, Ganesh Chandra Avenue, (2nd floor), Kolkata-13 for the following works in Malda under R.K.V.Y. from the bonafide experienced and resourceful contractors having experienced in such type of works in pure Govt. Department/Zilla Parishad.

| NIT | Name of the Work | Estimated Cost | Earnest Money | Place of Work. | Time of completion of work. |
|-----|--|--|---|------------------------------|---|
| 58 | Sinking of Tube-well with top enlargement with 150mm. dia. PVC Rigid Pipe with supplying and installation of 5-HP submersible Pump Motor set at Amrity Graft Nursery, Malda under R.K.V.Y. | Rs.2,68,527.00 (Rupees Two Lakh Sixty Eight Thousand Five Hundred Twenty Seven) Only. | Rs.6,720.00 (Rupees Six Thousand Seven Hundred Twenty) only. | Amrity Graft Nursery, Malda. | 1 (One) month from the date of issue of Work Order. |
| 59 | Under Ground PVC Pipe-line for Irrigation 80mm. dia. With spoit fitted with C.I. Sluice Valve with brick chamber at Amrity Graft Nursery, Malda. | Rs.4,99,026.00 (Rupees Four Lakh Ninety Nine Thousand Twenty Six) Only. | Rs.12,480.00 (Rupees Twelve Thousand Four Hundred Eighty) only. | -do- | -do- |

Tender papers (NIT), Priced Schedule & Form-2911(ii) etc. may be obtained / downloaded from seriwb.gov.org at free of cost.

| | |
|--|--|
| Last date & time of submission of Tender | 19-07-2019 upto 3-00 P.M. at Head Quarters, Kolkata. |
| Date & time of opening of Tender | 19.07.2019 upto 3-30 P.M. at Head Quarters, Kolkata. |


Tender should be submitted/dropped in the box kept at Head Quarters, Kolkata and papers should be arranged in the following manner.

Envelop - I, should be superscribed as Technical Bid for N.I.T No.....SL No. of Work. Name of agency and it should contain (Self Attested) PAN Card. Last I.T. Return, valid GSTIN Registration, P.Tax Challan. Credential (similar nature of work at about 60% of Tender Value) EMD etc. and sealed.

Envelop - II, should be super scribed as Financial Bid for N.I.T. No..... SL No. of Work. Name of Agency and should contain filled in - **2911 (ii)** quoting the Rate and Sealed.

2(two) envelopes as noted above (I & II) should be put in a bigger envelop and sealed. Agency should write clearly N.I.T. No., Name of Work, SL.No. and Name of Agency on this Envelope and drop the same as per schedule mentioned in this N.I.T. Technical Bid will be opened first. Financial Bid will be opened only if the technical Bid is found acceptable. Labour cess will be deducted from bill value as per Govt. Rules. All original copies are to be shown for verification. The details may be seen in the Office of the **Commissioner of Textiles(Sericulture), West Bengal**, 45, Ganesh Ch. Avenue (2nd floor), Kolkata-13 on any working days and web site seriwb.gov.org. The **Commissioner of Textiles(Sericulture), West Bengal** reserves the right to reject/cancel all the applications without showing any reasons thereof. If any date as above happens to be holidays the next working days will be considered as stipulated date. Acceptance of lowest tender is not obligatory.

N.S.C./K.V.P. will not be accepted as Earnest Money. Only the Bank Draft of a Nationalised Bank will be considered as Earnest money. Acceptance of lowest Tender is not obligatory. Notwithstanding anytime contained in this Notice Inviting Tender, the other terms & conditions and special terms & conditions will remain binding upon all concerned.


Executive Engineer,
Directorate of Sericulture,
West Bengal.

Price Schedule for sinking of Tube well with top enlargement of 150 mm dia PVC rigid pipe with supply and installation of SHP submersible pump motor at Amrity Sericulture Nursery, Malda Under RKVY

| Sl No | Description of Work | No.of Quantity | Unit | Rate Rs. | Amount Rs. |
|-------|---|---------------------|----------------|-------------------|----------------------|
| 01 | Labour for boring Tube well of required diameter with or without top enlargement up to the required depth as per direction of E.I.C. by water jet system through any type of soil starta including hire and labour charges for boring of pipes scaffolding other tools and plants as necessary and taking out them including lowering pipes, strainer, blind pipe etc. and fitted and fixed same complete including bucket washing and other incidental works in this connection. 150mm dia boring 80 mm dia boring | 30.00 30.00 | Mtr Mtr | 685.00 287.00 | 20550.00 8610.00 |
| 02 | Supply of PVC pipe & fittings (medium duty) conforming to ASTM-D-1785 and threaded to match with GI pipes as per IS:1239 (Part-I)(A)-(II) 19-III. 150mm dia boring 80 mm dia boring. | 30.00 18.00 | Mtr. Mtr. | 1420.00 578.00 | 42600.00 10404.00 |
| 03 | Supplying of high density polythene strainer of approved make with adapter conforming to I.S. specification (P-AV,lt.-5) 80 mm dia. | 12 m | Mtr. | 820.00 | 9840.00 |
| 04 | Supplying fitting and fixing heavy type bell mouth reducing socket. 75mm x 150 mm | 1 No. | Each | 616.00 | 616.00 |
| 05 | Supplying fitting and fixing plug of approved make conforming to IS specification 75 mm dia. | 1 No | Each | 130.00 | 130.00 |
| 06 | Supplying fitting and fixing G.I. cap at top 150 mm dia. | 1 No. | Each | 503.00 | 503.00 |
| 07 | Packing the annular space between the outside of the tube well pipes and strainers and the bore with pea size washed gravel of approved quality having size from 2 mm to 5 mm or the size approved by the Engineer Incharge including cost of all materials labour and equipment complete. | 0.90 m ³ | M ³ | 2029.00 | 1826.00 |
| 08 | Supplying fitting and fixing 300mm M.S. housing clamp of approved quality. | 1 No | set | 2235.00 | 4470.00 |
| 09 | Supplying fitting and fixing steel cutter pipe up to 450 mm long with shocket 75 mm dia. | 1 No | Each | 403.00 | 403.00 |
| 10 | Washing and developing tube well with air compressor pump and engine for 8 (eight) hours continuous pumping per day with necessary arrangements for testing the yield in gallons per hour with 'V'notch including hire and labour charges for all ;ltools and plants and scaffolding as required. | 2 | Day | 7538.00 | 15076.00 |
| 11 | Collecting sample of water for bacteriological and chemical test for any depth at any time during execution of work including hire and labour charges for tools and aplants and sterilizing the equipments, paying all charges and fees, testing etc. complete in all respect as per direction. L.S. | 1 | Each | 1231.00 | 1231.00 |
| 12 | Supply & of towering 5 H.P 3 Ph. Submersible pump-Motor set of TEXMO (Model No. HMF 60/12) in the existing well | 1 | Each | 37261.00 | 37261.00 |
| 13 | Supply & fitting submersible cable suitable for 6 H.P. 3 Hp. ;submersible Pump-Motor. | 50.00 | Mtr. | 109.72 | 5486.00 |
| 14 | Supply and fitting control panel suitable for 5 H.P. 3 PH. Submersible Pump Motor L&T make on angle iron ;frame as wall. | 1 | Each | 6102.00 | 6102.00 |

ay ay

| | | | | | |
|----|---|----------------|--------------|----------------------|---------------------|
| 15 | Supply of 65mm dia G.I. column I and other works. | 35.00 | Mtr. | 606.00 | 21210.00 |
| 16 | Supply of 65mm dia GI socket for column pipe | 9 | Each | 172.00 | 1548.00 |
| 17 | Supply of 65 mm dia GI bend. | 2 | Each | 846.00 | 1692.00 |
| | Supply of 65 mm dia GI "T" pipe. | 1 | Each | 313.00 | 313.00 |
| 19 | Supplying fitting and fixing G.I. pipes of TATA make with all necessary accessories, specials viz socket bend tee, union, cross, elbo, nipple, long screw, reducing socket, reducing tee, short piece etc fitted with holder bats clamps, including cutting pipes making threads fitting, fixing etc. complete in all respect. i) 25 mm dia medium Quality. ii) 50 mm dia medium quality. | 15.00 30.00 | Mtr. Mtr. | 305.00/m 540.00/m | 4575.00 16200.00 |
| 20 | Supplying & Fitting 80 mm M.S. Clamp with Suitable nuts and bolts. | 1.00 | Each. | 520.00 | 520.00 |
| 21 | Supply & fitting M.S. Well cover. 150 x 80 mm | 1.00 | Each | 866.25 | 866.00 |
| 22 | Earthing the whole installation by 2 " dia 10' long GI Pipe and as per PWD schedule. | 2.00 | Each | 1524.00 | 3048.00 |
| 23 | Supply & Fitting 32A TPN Main switch (HAVELLS) with fuses on LS & NL on angle iron frame on wall. | 1.00 | Each | 2464.00 | 2464.00 |
| 24 | Supply & Laying 4 core 16 sq. Mm PVC/A cable partly in the under ground trench as per PWD schedule from O.H. line to Main switch. | 45.00 | Mtr. | 315.00 | 14175.00 |
| 25 | Supply & fitting 32 mm dia protection pipe as per PWD schedule. | 12.00 | Mtr. | 218.00 | 2616.00 |
| 26 | Supply & fitting Steel strain wire with PVC coted for fixing of pump. | 30.00 | Mtr. | 110.00 | 3300.00 |

Rs. 237635.00

Add G.S.T. 12 % (+) Rs. 28516.00

Rs. 266151.00

Add Labour Cess 1 % (+) Rs. 2376.00

Rs. 268527.00



Executive Engineer
Directorate of Textiles (Sericulture)
West Bengal.