

Invitation of Tender Notice Nos.88, 89 & 90/Seri/Eng/Civil/PCR/DD/2019-'20.

Sealed Tenders are invited by the Executive Engineer, Sericulture, West Bengal, 45, Ganesh Chandra Avenue, (2nd floor), Kolkata-13 for the following works in the district of Dakshin Dinajpore from the bonafide experienced and resourceful contractors having experienced in such type of works in pure Govt. Department / Zilla Parishad.

NIT	Name of the Work	Estimated-Cost	Earnest Money	Place of Work.	Time of completion of work.
88	Construction of Chain-link Fencing with R.C.C. Post at M.M.Farm, Kumarganj, Dakshin Dinajpore under P.C.R.	Rs.4,26,049.00 (Rupees Four Lakh Thirty Ninety Nine thousand Eight M) hundred Ninety Four) only.	Rs.10,655.00 (Rupees Ten Thousand Six Hundred Fifty Five) only.	M.M. Farm, Kumarganj, Dinajpore.	1 (One) month from the date of issue of Work Order.
89	Repairing works of sloped roof Rearing House at T.D. Farm, Balapur Dakshin Dinajpore under P.C.R.	Rs.4,99,814.00 (Rupees Four Lakh Ninety Nine thousand Eight Hundred Fourteen)only.	Rs.12,495.00 (Rupees Twelve thousand Four Hundred Ninety Five)Only	T.D. Farm, Balapur, Dakshin Dinajpore.	-do-
90	Repairing of Boundary wall (broken portion) at M.M.Farm, Kumarganj, Dakshin Dinajpore under P.C.R.	Rs.76,154.00 (Rupees Seventy Six Thousand One Hundred Fifty Four)only.	Rs.1,905.00/- (Rupees One Thousand Nine Hundred Five)only,	M.M. Farm, Kumarganj, Dinajpore.	-do-

Tender papers (NIT), Priced Schedule & Form-2911(ii) etc. may be obtained/downloaded from

of cost.

seriwbgov.org at free

The second secon	 00///
Last date & time of submission of Tender	2401-2020 upto 3-00 P.M. at Head Quarters, Kolkata.
Date & time of opening of Tender	 24.01.2020 upto 3-30 P.M. at Head Quarters, Kolkata.

Tender should be submitted / dropped in the box kept at Head Quarters, Kolkata and papers should be arranged in the following manner.

Envelop - I, should be superscribed as Technical Bid for N.I.T No......SL No. of Work, Name of agency and it should contain (Self Attested) PAN Card. Last I.T. Return, valid GSTIN Registration, P.Tax Challan, Credential (similar nature of work at about 60% of Tender Value) EMD & etc. and sealed.

Envelop - II, should be super scribed as Financial Bid for N.I.T. No. SL No. of Work, Name of Agency and should contain filled in - 2911 (ii) quoting the Rate and Sealed.

2(two) envelopes as noted above (1 & II) should be put in a bigger envelop and sealed. Agency should write clearly N.I.T. No., Name of Work, SL.No. and Name of the Agency on this Envelope and drop the same as per schedule mentioned in this N.I.T.

Technical Bid will be opened first. Financial Bid will be opened only if the technical Bid is found acceptable.

Labour Cess will be deducted from bill value as per Govt. Rules. All original copies are to be shown for verification. The details may be seen in the Office of the Commissioner of Textiles (Sericulture), West Bengal, 45, Ganesh Ch, Avenue (2nd floor), Kolkata-13 on any working days and web site *seriwbgov.org*. The Commissioner of Textiles (Sericulture), West Bengal reserves the right to reject/cancel all the applications without showing any reasons thereof. If any date as above happens to be holidays the next working days will be considered as stipulated date. Acceptance of lowest tender is not obligatory.

N.S.C./ K.V.P. will not be accepted as Earnest Money Only the Bank Draft of a Nationalised Bank will be considered as Earnest money. Acceptance of lowest Tender is not obligatory.

Notwithstanding anytime contained in this Notice Inviting Tender, the other terms & conditions and special terms & conditions will remain binding upon all concerned.

Executive Engineer,
Directorate of Sericulture,
West Bengal.

Fice Schedule for Construction of chain link fencing with RCC post (precast) at M.M.Farm Kumarganj in the District of Dakshin Dinajpur (L-105.00 M).

	Kumarganj in the District of Dakshin Dinajpur (L-			
SI No.	PARTICULARS	QTY.	RATE	AMOUNT.
01	Uprooting and removing plants from the surface plants of girth above 150mm but not exceeding 225 mm.	35 Nos.	187.00	6545.00
02	Cleaning compound premises of shrubs, plants, junges etc. by ;cutting and removing as directed. (specific permission of E.I.O prior to execution will be necessary)	105m ³	11.00	1155.00
03	Ordinary cement concrete (Mix 1:1.5:3) with graded stone chips (20 mm dia) excluding shuttering and reinforcement if any pakur variety.	5m³	6598.30/m ³	32992.00
04	Reinforcement for reinforced concrete work in all sorts of structure including distribution bars, stirrups, binder etc. including supply of rods, initial strengthening and removal of loose rust (if necessary) rust cutting to requisite length hooking and bending to correct shape, ;placing in proper position and binding with 16 gauge black annealed wire at every intersection complete as per drawing and as directed.	0.50MT	60205.00	30103.00
05	Hire and labour charges charges for shuttering with thick hard wood for precast RC slab etc. and striking out the same incl. fitting, fixing the precast slab in position with necessary carriage and haulage, hoisting etc. complete in all respect.	100m ²	93.00/m ²	9300.00
06	Fixing post of iron or precast concrete by digging hole in ;the ground (in all sorts of soil) and embedding the same by packing the hole with cement concrete (6:3:1) (with Jhamakhoa) and finishing the top surface to regular shape as directed, with cement plaster (6:1) complete including the cost of concrete, plaster etc. but excluding the cost of the post.Av.Dia of hole 400 mm dia. Depth not exc.750mm.	84 Nos	421.00/each	35364.00
07	Earth work in excavation of foundation trenches or drain in all sorts of soil including removing, spreading or stacking the spoils, within a lead of 75. As directed. Depth of excavation not exceeding 1.50m.	13m ³	119.27/m³	1551.00
08	Supplying and laying polythene sheet (150gm/m²) over in foundation trenches.	29m²	24.00/m ²	696.00
09	Cement concrete with 30 mm down graded shingles excluding shuttering in G.F.(1:3:6) proportion.	20m³	5461.00/m ³	109220.00
10	Hire and labour charges for shuttering with centering and necessary staging up to 4 m and thick hard wood planks of approved thickness with required bracing for concrete slab, beams etc. including fitting and fixing and striking out after completion of works. 25mm to 30 mm shuttering without shuttering without staging.	147m²	205.00/m ²	30135.00
		<u> </u>	(D) (2	

Contd......(P).....(2).....

		-		
12	Plaster (to wall, floor, ceiling etc.) with centering and cement mortar including rounding off or chamfering corners as directed and racking out joints or roughening of surface including threating, nosing and drip course where necessary (A) In G.F. (i) With sand and cement mortar (4:1) 15 mm thick (ii) With sand (6:1) cement mortar 20mm thick Neat cement punning about 1.5 mm thick in wall, dado window sills, floor, drain etc.	75m ² 165m ²	157.00/m ² 162.00m ² 34.00/m ²	11775.00 26730.00 5610.00
13	Protection and Decorative Acrylic exterior emulsion paint of approved quality as per direction of E.I.C. Normal Acrylic Emulsion.	75m ²	97.00/m ²	7275.00
14	S/F/F chain link fencing of approved quality with RCC post by means of galvanized high tension spring steel wire of 12 S.W.G.which have to be tensioned and fixed to the vertical post by menas of galvanized special clips bolts and nut etc. 75 mm x 75 mm x 8g.	157.50m ²	335.00/m ²	52763.00
15	M.S.structural works in columns, became etc. with simple rooled sttuctural members joins, angle channel section connected to one another etc. including cutting to requisite shape and length fabrication with necessary bolting etc. including all incidental changes etc.	0.126MT	60230.00/MT	7589.00
16	S/F/F bolts with nuts, washer 10 to 16 mm dia. Length above 150 to 200m	63kg.	114.00/kg	7182.00
17	Surface dressing of the ground in any kind of soil etc. up to 15 cm depth etc.	105 m ²	10.00/kg	1050.00
18	Painting with best quality synthetic enamel paint of approved make and brand incl. smoothening surface by sand papering etc. including using of approved putty etc.on the surface4, 2 coat if necessary.	5m ²	79.00/m ²	395.00

Rs. 3,77,430.00

Add G.S.T. 12 % (+)

Rs. 45,292.00

Rs. 4,22,722.00

Add labour welfare cess 1 %

Rs. 4,227.00 Rs. 4,26,949.00

Executive Engineer

Directorate of Textiles (Sericulture)

West Bengal.