

GOVERNMENT TENDER NOTICE

Notice Inviting Tender Nos.110,111,112,113,114,115,116 & 117/SERI/PCR/MID(W)/2017-'18.

Sealed quotations are invited by the Executive Engineer, Directorate of Textiles(Sericulture), West Bengal, 45, Ganesh Chandra Avenue (2nd floor), Kolkata-13 for Constructional works in Paschim Medinipur district from the enlisted contractors of P.W.D. (Elec.), CB Directorate, as well as from the bonafide experienced and resourceful outside contractors having experience in such type of works in Govt. Department / Zilla Parishad.

| NIT No. | Name of the Work. | Estimated Cost | Earnest Money | Place of Work. | Time of completion of work. |
|---------|---|--|---|--|--|
| 110 | Repairing of Grainage Building at Debra Sericulture Complex. Paschim Medinipur under P.C.R. works. | Rs.4.73.267/- (Rupees four lakh seventy three thousand two hundred sixty seven) only. | Rs.11.835/- (Rupees eleven thousand eight hundred thirty five) only. | Debra Sericulture Complex. Paschim Medinipur. | 1(one) month from the date of issue of Work Order. |
| 111 | Renovation of Toilet Block at Neguria Tasar Project Centre, Banspahari, Paschim Medinipur under P.C.R. | Rs.3.27,210/- (Rupees three lakh twenty seven thousand two hundred ten) only. | Rs.8,180/- (Rupees eight thousand one hundred eighty) only. | Neguria Tasar Project Centre, Banspahari, Paschim Medinipur. | -do- |
| 112 | Repairing of Office Building of the Deputy Director of Textiles(Sericulture), Paschim Medinipur under P.C.R. | Rs.3.44,522/- Rupees three lakh forty four thousand five hundred twenty two) only. | Rs.8,615/- (Rupees eight thousand six hundred fifteen) only. | Office of the Deputy Director, Textiles (Seri.), Paschim Medinipur | -do- |
| 113 | Repairing of Cocoon Market Building at Debra, Paschim Medinipur. under P.C.R. | Rs.4,25,801/- (Rupees four lakh twenty five thousand eight hundred one) only. | Rs.10,645 - (Rupees ten thousand six hundred forty five) only. | Debra Cocoon Market, Debra Paschim Medinipur. | -do- |
| 114 | Repairing of Cocoon Market-cum-Office Building at Belpahari T.S.C., Paschim Medinipur, under P.C.R. | Rs.4,28,462/- (Rupees four lakh twenty eight thousand four hundred sixty two) only. | Rs.10,715/- (Rupees ten thousand seven hundred fifteen) only. | T.S.C., Belpahari, Paschim Medinipur. | -do- |
| 115 | Sanitary & Plumbing works with allied works for the existing Grainage Building at Debra, Paschim Medinipur under P.C.R. | Rs.4,23,084 /- (Rupees four lakh twenty three thousand eighty four) only. | Rs.10,580/- (Rupees ten thousand five hundred eighty) only. | Debra Sericulture Complex, Paschim Medinipur. | -do- |
| 116 | Anti-termite treatment for Cocoon Market Building at Debra in Paschim Medinipur under P.C.R. works. | Rs.70,937/- (Rupees seventy thousand nine hundred thirty seven) only. | Rs.1,775/- (Rupees one thousand seven hundred seventy five) only. | Cocoon Market Complex, Debra Paschim Medinipur. | -do- |
| 117. | Anti-termite treatment for the Office Building of the Deputy Director of Textiles(Sericulture), Paschim Medinipur under P.C.R. works. | Rs.53,879/- (Rupees fifty three thousand eight hundred seventy nine) only. | Rs.1,350/- (Rupees one thousand three hundred fifty) only. | Office Building of the Deputy Director of Textiles(Seri.), Paschim Medinipur | -do- |

The quotation Papers (N.I.T., Schedule of Works, & Form : 2911(i/ii) etc.) may be obtained/downloaded from seriwb.gov.org at free of cost. Duly filled quotation to be submitted/dropped in the Box kept at Head Quarters, Kolkata and papers should be arranged in the following manner.

Envelope - I, should be superscribed as Technical Bid for N.I.T. No. SI.No. of Work. Name of the Agency and it should contain copy of Self Attested i) PAN Card. (ii) Last I.T. Return. (AY 2016-17) (iii) GST IN Registration Certificate which is valid for the current period. (iv) Professional Tax Clearance and Challan for the last

financial year, (v) Credential for Similar nature of work at about 60% of Tender value) and the Pesticide License for N.I.T. Nos.116 & 117 respectively and E.M.D. Sealed.

Envelope - II, should be super scribed as Financial Bid for N.I.T.No....., Sl.No. of Work, Name of Agency and should contain filed on **2911 (ii)** quoting in Rate both in figure and words, and Sealed.

2(two) Envelopes as noted above (**I & II**) should be put in a bigger Envelope and sealed. Agency should write clearly N.I.T. No..... Name of Work, SL. No. and Name of Agency on this Envelope and drop the same as per scheduled mentioned in this N.I.T.

| | |
|---|---|
| Last date and time of submission of Tender | 28-03-2018 at 3-00 P.M. at Headquarters, Kolkata. |
| Date of opening of Tender | 28.03.2018 at 3-30 P.M. at Headquarters, Kolkata. |


Technical Bid will be opened first. Financial Bid will be opened only if the Technical Bid is found acceptable.

Labour Cess will be deducted from Bill value as per Govt. Rules. All original copies are to be shown for verification. The details may be seen in the Office of the **Commissioner of Textiles (Sericulture), West Bengal** 45, Ganesh Ch. Avenue (2nd floor), Kolkata - 700 013 on any working days and in website : seriwb.gov.org.

N.S.C./K.V.P. will not be accepted as Earnest Money. Only the Demand Draft / Bankers Cheque of a Nationalized Bank will be considered.

The Commissioner of Textiles (Sericulture), West Bengal reserves the right to reject/accept all the applications without showing any reasons thereof. If any date as above happens to be holiday the next working day will be considered as stipulated date. Acceptance of lowest Tender is not obligatory.

Notwithstanding anything contained in this N.I.T., the general and other terms and conditions will be binding upon all concerned.



 Executive Engineer,
 Directorate of Textiles(Sericulture),
 West Bengal.

Memo.No: 4042(3) (ENG/CIVIL/PCR/MID(W)/5 (Vol.-3),

Dated, 21/02/2018.

Copy forwarded for information & necessary action to :-

1. The Deputy Director of Textiles (Sericulture), Paschim Medinipur.
2. The Notice Board of this Directorate, Headquarters, Kolkata.
- ✓ 3. The Website of this Directorate of Textiles (Sericulture), West Bengal.



 Executive Engineer,
 Directorate of Textiles (Sericulture),
 West Bengal.

Priced Schedule for the Repairing of Cocoon market cum office building at Belpahari TSC Office, Belpahari, Midnapur (West) under PCR.

| Sl. no | Description of work | Unit | Quantity | Rate | Amount |
|--------|--|------|----------|---------|----------|
| 1 | Dismantling artificial stone flooring upto 50 mm. thick by carefully chiselling without damaging the base and removing rubbish as directed within a lead of 75 m. | Sqm | 60.00 | 50.00 | 3000.00 |
| 2 | Stripping off worn out plaster and raking out joints of walls, celings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed.ground floor including roof. | Sqm | 270.00 | 19.00 | 5130.00 |
| 2 | Labour for taking out door and window frame including shutter for repair or replacement of different parts of the frame & refixing the same including mending good all damaes complete. (Concrete and brick work for mending damage will be paid separately) | Sqm | 15.00 | 126.00 | 1890.00 |
| 4 | Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[(i). With 1:4 cement mortar, 20 mm thick plaster. In Ground floor | Sqm | 80.00 | 172.00 | 13760.00 |
| 5 | Plaster (to wall, floor, ceiling etc.) with sand and cement mortar (i). With 1:4 cement mortar, 20 mm thick plaster. In Firs floor | Sqm | 33.00 | 176.00 | 5808.00 |
| 6 | Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed (i). With 1:4 cement mortar, 15 mm thick plaster.(Ground floor).[| Sqm | 100.00 | 150.00 | 15000.00 |
| 7 | Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed (i). With 1:4 cement mortar, 15 mm thick plaster. In first floor | Sqm | 55.00 | 154.00 | 8470.00 |
| 8 | Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed [(i). With 1:4 cement mortar, 10 mm thick plaster. In Ground floor | Sqm | 55.00 | 122.00 | 6710.00 |
| 9 | Shutters of 2/3rd panel and 1/3rd glazed of doors and windows as per design (each panel consisting of a single plank without joint and with ordinary glass of 7.4kg. Per sq.m./3mm thick) fitted with putty bed and teak wood beads and nails including fitting and fixing shutters in position but excluding the cost of glass , putty , teak bead, nails, hinges etc. and other fittings, in ground floor. | Sqm | 3.00 | 3046.00 | 9138.00 |
| 10 | Supplying and laying true to line and level vitrified tiles of approved brand (size not less than 600 mm X 600 mm X 10 mm thick) in floor, skirting etc. set in 20 mm sand cement mortar (1:4) and 2 mm thick cement slurry back side of tiles using cement @ 2.91Kg./sqM or using polymerised adhesive (6 mm thick layer applied directly over finished artificial stone floor/Mosaic etc without any backing course) laid after application slurry using 1.75 Kg of cement per sqM below mortar only, including the cost of materials, labour and all other incidental charges complete true to the manufacturer's specification and direction of Engineer-in-Charge.(White cement, synthetic adhesive and grout material to be supplied by the contra ctor. | Sqm | 23.00 | 1369.00 | 31487.00 |
| 11 | Brick work with 1st class bricks in cement mortar (1:4) n superstructure G.F. | Cum | 1.60 | 5594.00 | 8950.00 |

07/13/18
Executive Engineer,
Directorate of Textiles (Sericulture),
West Bengal

| | | | | | |
|----|--|-----|--------|---------|----------|
| 12 | Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) | Sqm | 15.00 | 321.00 | 4815.00 |
| 13 | Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. (i) Pakur Variety | Cum | 8.50 | 6479.00 | 55071.00 |
| 14 | Single Brick Flat Soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand. | Sqm | 50.00 | 343.00 | 17150.00 |
| 15 | Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. | kg | 125.00 | 55.63 | 6954.00 |
| 16 | Neat cement punning about 1.5mm thick in all, dado, window sill, floor etc. | Sqm | 80.00 | 34.00 | 2720.00 |
| 17 | Supplying fitting and fixing in position approved P.V.C. door frame (Matt finish) made of extruded P.V.C. multichamber hollow section having dimensions 60mm x 50mm x 2mm (+/- 0.2mm), horizontal section will be joined with vertical section by galvanised steel screws after inserting two number steel brackets as reinforcement making suitable space for placing hinges, one steel tube 40mm x 20mm x 1.20 mm will be inserted on one full vertical side of the frame (hinge side) as reinforcement, the frame will then be fixed in the opening with the help of P.V.C. expandable fastner/wooden gutties and galvanised steel screws including cost of all materials and labour, hire charges of tools and appliances, carriage of all materials, taxes and all other incidental charges complete. | m | 15.00 | 279.00 | 4185.00 |
| 18 | PVC Door Shutter-30 mm thick: Supplying fitting and fixing P.V.C. door shutter of approved quality & shade in position, the style & rail of the P.V.C. door shutter will be made of rigid P.V.C. multicavity hollow chamber of 59 mm x30 mm section with 2.0 mm (+/-0.2 mm) wall thickness. Horizontal & vertical section shall be fixed to each other by self tapping screws and 1 solid polymeric or M.S. galvanised tubular 'L' shaped bracket 100mm x 200mm in each corner of the shutter frame for placing hinges. Polymer based multicavity hollow section of 120 mm x30mm with 2.0 mm (+/- 0.2 mm) wall thickness will be fitted in the middle, reinforced by solid polymer bar of 200 mm long at both ends and screws from both sides as lock rail. | Sqm | 5.00 | 2127.00 | 10635.00 |
| 19 | Panel shutters of door and window, as per design (each panel consisting of single plank without joint), including fitting and fixing the same in position but excluding the cost of hinge and other fittings. In ground floor. | Sqm | 1.75 | 2789.00 | 4881.00 |
| 20 | White washing including cleaning and smoothening surface 3 coats thoroughly. In Ground Floor | Sqm | 400.00 | 18.14 | 7256.00 |
| 21 | Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothening of surface. Two Coats | Sqm | 140.00 | 70.00 | 9800.00 |
| 22 | Applying Exterior grade Acrylic primer of approved quality and brand on plastered or concrete surface old or new surface to receive decorative textured(matt finish) or smooth finish acrylic exterior emulsion paint including scraping and preparing the surface throughly, complete as per manufacturer's specification and as per direction of the EIC.. In Ground floor. | Sqm | 195.00 | 31.40 | 6123.00 |
| 23 | Applying Exterior grade Acrylic primer of approved quality in First floor | Sqm | 206.00 | 32.11 | 6615.00 |


 Executive Engineer,
 Directorate of Textiles (Sericulturte),
 West Bengal

| | | | | | |
|----|--|------|--------|---------|----------|
| 24 | Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of EIC to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer. In Ground floor. | Sqm | 195.00 | 84.00 | 16380.00 |
| 25 | Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification | Sqm | 206.00 | 84.71 | 17450.00 |
| 26 | Supplying, fitting & fixing 1st quality Ceramic tiles in walls and floors to match with the existing work & 4 nos. of key stones (10mm) fixed with araldite at the back of each tile & finishing the joints with white cement mixed with colouring oxide if required to match the colour of tiles including roughening of concrete surface, if necessary or by synthetic adhesive & grout materials etc. | Sqm | 15.00 | 731.00 | 10965.00 |
| 27 | Supplying, fitting & fixing 1st quality Ceramic tiles in walls and floors to match with the existing work. In Wall | Sqm | 37.00 | 738.00 | 27306.00 |
| 28 | Supplying, fitting and fixing white vitreous china best quality approved make wash basin with C.I. brackets on 75 mm X 75 mm wooden blocks, C.P. waste fittings of 32 mm dia., one approved quality brass C.P. pillar cock of 15 mm dia., C.P. chain with rubber plug of 30 mm dia., approved quality P.V.C. waste pipe with C.P. nut 32 mm dia., 900 mm long approved quality P.V.C. connection pipe with heavy brass C.P. nut including mending good all damages | Each | 3.00 | 2208.00 | 6624.00 |
| 29 | Supplying, fitting and fixing Anglo-Indian W.C. in white glazed vitreous china ware of approved make complete in position with necessary bolts, nuts etc. | Each | 1.00 | 3287.00 | 3287.00 |
| 30 | Supplying, fitting and fixing Orissa pattern W.C. in white glazed vitreous china ware of approved make complete in position (i) 580 mm X 440 mm | Each | 2.00 | 1613.00 | 3226.00 |
| 31 | Supplying, fitting and fixing Flat back urinal (half stall urinal) in white vitreous chinaware of approved make in position with brass screws on 75 mm X 75 mm X 75 mm wooden blocks complete. 590 mm X 390 mm X 380 mm | Each | 3.00 | 945.00 | 2835.00 |
| 32 | Supplying, fitting and fixing towel rail with two brackets. 750 mm long 25mm dia. | Each | 3.00 | 430.00 | 1290.00 |
| 33 | Supplying, fitting and fixing 10 litre P.V.C. low-down cistern conforming to I.S. specification with P.V.C. fittings complete, C.I. brackets including two | Each | 3.00 | 1015.00 | 3045.00 |
| 34 | Supplying, fitting and fixing PVC pipes of approved make of (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, long screw, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, making threads, fitting, fixing etc. complete in all respect 20 mm dia | m | 15.00 | 129.00 | 1935.00 |
| 35 | Supplying, fitting and fixing PVC pipes of approved make of (medium duty) conforming to ASTM D - 1785, 15 mm dia | m | 15.00 | 101.00 | 1515.00 |
| 36 | Supplying, fitting and fixing bib cock or stop cock. (a) (i) Chromium plated Bib Cock short body (Equivalent to Code No 511 & Model - Tropical / Sumthing Special of ESSCO or similar brand). | Each | 3.00 | 539.00 | 1617.00 |
| 37 | Chromium plated Stop Cock (Equivalent to Code No. 513(A) & 513(B) & Model - Tropical / Sumthing Special of ESSCO or similar | Each | 6.00 | 674.00 | 4044.00 |
| 38 | Supplying, fitting and fixing best quality Indian make mirror 5.5 mm thick with silvering as per I.S.I. specifications supported on fibre glass frame of any colour, frame size 550 mm X 400 mm | Each | 3.00 | 367.00 | 1101.00 |
| 39 | Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc. | Sqm | 85.00 | 38.00 | 3230.00 |

06/13/18

Executive Engineer,
Directorate of Textiles (Sericulture),
West Bengal

| | | | | | |
|--|---|------|-------|--------|--------------------|
| 40 | Priming one coat on Steel or other surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc. | Sqm | 25.00 | 29.00 | 725.00 |
| 41 | Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary on timber or plastered surface. | Sqm | 85.00 | 81.00 | 6885.00 |
| 42 | Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. on Steel or other metal surface. | Sqm | 25.00 | 79.00 | 1975.00 |
| 43 | Iron butt hinges of approved quality fitted and fixed with steel screws, with ISI mark. 100mmx58mm x 1.25 mm | Each | 3.00 | 43.00 | 129.00 |
| 44 | Iron butt hinges of approved quality fitted and fixed with steel screws, with ISI mark. 75mm x 47mm x 1.7mm | Each | 12.00 | 31.00 | 372.00 |
| 45 | i) Iron hasp bolt of approved quality fitted and fixed complete (oxidised) with 16mm dia rod with centre bolt and round fitting.300 mm long. | Each | 1.00 | 166.00 | 166.00 |
| 46 | Artificial stone in floor, dado, staircase etc with cement concrete (1:2:4) with stone chips, laid in panels as directed with topping made with ordinary or white cement (as necessary) and marble dust in proportion (1:2) including smooth finishing and rounding off corners | Sqm | 45.00 | 328.00 | 14760.00 |
| 47 | Supplying, fitting and fixing approved brand 32 mm dia. P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps. | Each | 3.00 | 89.00 | 267.00 |
| | Dismantling artificial stone flooring upto 50 mm. thick by carefully chiselling without damaging the base and removing rubbish as directed within a lead of 75 m. | | | | |
| 48 | Supplying, fitting and fixing cast iron 'P' or 'S' trap conforming to I.S. 3989 / 1970 and 1729 / 1964 including lead caulked joints and painting two coats to the exposed surface. (Painting to be paid seperately). | Each | 2.00 | 803.00 | 1606.00 |
| 49 | Supplying, fitting and fixing Closet seat of approved make with lid and C.P. hinges, rubber buffer and brass screws complete. | Each | 1.00 | 485.00 | 485.00 |
| | | | | | 378768.00 |
| | | | | | 45452.00 |
| | | | | | 424220.00 |
| | | | | | 4242.00 |
| | | | | | 428462.00 |
| | | | | Say | 4,28,462.00 |
| Rupees Four lakhs twenty eight thousand four hundred sixty two only. | | | | | |

04/6/18
Executive Engineer

Directorate of Textiles (Sericulture)
West Bengal