

## Government Tender Notice

N.I.Q. No. 15 /SERI/PCR/MSD/2017-'18.

Sealed Quotations are invited by the Executive Engineer, Sericulture, West Bengal, 45, Ganesh Chandra Avenue (2nd floor), Kolkata-13 for the following works at Sericulture Unit in the district of Murshidabad under P.C.R. from the bonafide experienced and resourceful contractors having experienced in such type of works in pure Govt. Department/Zilla Parishad.

N.I.Q. No.	Name of the Work.	Earnest Money	Place of Work.
15	Shifting of existing Walk-in-Cold Room from Akherighata Sericulture Complex & Re-installation of Walk-in-Cold Room at Regional Grainage, Berhampore in Murshidabad under P.C.R.	2.50 % (Two point five zero) percent of the quoted value.	Akherighata Sericulture Complex, Berhampore, Murshidabad & Berhampore Regional Grainage Complex, Murshidabad.

Quotation Papers (NIQ, Priced Schedule & Form : 2911(ii) etc.) may be obtained/downloaded from [seriwb.gov.org](http://seriwb.gov.org) at free of cost.

Quotation should be submitted/dropped in the Box kept at Head Quarters, Kolkata and papers should be arranged in the following manner.

Last date and time of submission of Quotation	29-03-2018 upto 3-00 P.M. at Headquarters. Kolkata.
Date and time of opening of Quotation	29-03-2018 at 3-30 P.M. at Headquarters. Kolkata


**Envelope - I**, should be super scribed as Technical Bid for N.I.Q.No....., Sl.No. of work. Name of the Agency that it should contain ( Self Attested ) i) PAN Card. Last I.T. Return, GST IN, P.T. Challan, Credential (Similar nature of work at about 60% of Tender value), E.M.D and sealed.

**Envelope - II**, should be super scribed as Financial Bid for N.I.Q. No....., Sl.No. of work, Name of Agency and should contain filed on 2911 (ii) quoting in Rate and Sealed.

2(two) Envelopes as noted above (I & II) should be put in a bigger Envelope and sealed. Agency should write clearly N.I.Q. No..... Name of Work, SL. No. and Name of Agency on this Envelope and drop the same as per scheduled mentioned in this N.I.Q.

Technical Bid will be opened first. Financial Bid will be opened only if the Technical Bid is found acceptable. Labour Cess will be deducted from Bill value as per Govt. Rules. All original copies are to be shown for verification. The details may be seen in the Office of the **Commissioner of Textiles (Sericulture), West Bengal, 45, Ganesh Ch. Avenue (2nd floor), Kolkata - 13** on any working days and in website : [seriwb.gov.org](http://seriwb.gov.org). The Commissioner of Textiles (Sericulture), West Bengal reserves the right to reject/accept all the applications without showing any reasons thereof. If any date as above happens to be holiday the next working day will be considered as stipulated date. Acceptance of lowest Tender is not obligatory.


N.S.C./K.V.P. will not be accepted as Earnest Money. Only the bank Draft of a Nationalized Bank will be considered.

  
Executive Engineer,  
Directorate of Textiles(Sericulture),  
West Bengal,  
Dated, 27/02/2018.

Memo.No. 4066(B) ENG/CIVIL/PCR/MSD/4(Vol.-5)

Copy forwarded for information & necessary action to :-

1. The Deputy Director of Textiles (Sericulture), Berhampore, Murshidabad.
2. The Notice Board of this Directorate, Headquarters, Kolkata.
3. The **Website** of this Directorate of Textiles (Sericulture), West Bengal.

  
Executive Engineer,  
Directorate of Textiles(Sericulture),  
West Bengal.

## Specification of works

Shifting of existing Walk-in-Cold Room from Akherighata Sericulture Complex, District, Murshidabad and Re-installation at Berhapore Regional Grainage, Murshidabad. (Walk-in-Cold Room with 20 KVA 3-Ph Generator, & 15 KVE Servo (3-Ph Controller).

Sl.No.	Particulars items of Works.
1.	5 Unit 3 Ton A/C split set indoor & outdoor, Total open & new installation
2.	5 Unit set total Brass pipe open & new installation & extra extension 5/8 size 40' & 3/8 40' Brass pipe installation.
3.	5 Unit 3 Ton A/C split set gas charging R-20, 15 KG. 5 Nos. Silkajel Filter change.
4.	5 Nos. outdoor Unit Wall clame & pipe insulator.
5.	Electronics Thurmostar Total open & new installation
6.	One 15' /8' Egg Cold Room & Cold Anti-chamber Total open & new installation.
7.	One 10' /7' Egg Cold Room Total open & new installation.
8.	20KVA, 3 Ph Generator open & new installation with Generator Platform & shed open & new installation.
9.	Main Electrical cable line open & new installation.
10.	Main switch & servo control (15 KVA) & N.C.P. Board open & Total new installation.
11.	Cold-Room light & Electrical lilne & Switch Board open & new installation.


### Description of the Plant :

1. Split type air-cooled condensing unit installed outside for each matching indoor evaporator Unit with R404A-Refrigerant, Sealed Compressors, Control Panel.
2. 60 MM thick PUF Paneled Chambers of following specification.

	Egg Room	Ante Room	Moth Preservation Room
Size	2400 x 2400 x 2500 MM	2400 x 2400 x 2500 MM	2400 x 2400 x 2500 MM
Temperatures to be maintained.	0 to 5°C	10 to 15 °C	5°C to 10 °C
Refrigeration Capacity	15000 Btu/hr	10000 Btu/hr	15000Btu/hr
No. of Units.	2 (1 Working + Standby)	1 Only	2(1 Working + 1 Standby.

3. Diesel Generator set, 3 Phase, 415 Volt, 50 Hz, mounted on iron base frame with 150 Liters, Diesel Tank, maintenance free Battery with connected cables having a capacity of 20 KVA with matching alternator in Acoustic Enclosure - 1 No.
4. Servo Controlled 3 Phase, 4 Wire, 415 Volt, 50 Hz, 12 KVA Voltage Stabilizer with input Voltage 300 to 465 Volts and Output Voltage 400 to 415 Volts - 1 No.

Under otherwise specified all works shall be carried out in accordance with Indian Electricity Act-1910, Indian Electricity Rules, 1956 with amendments or any revision thereof which may be issued during the currency of the contact & the requirement of any other rules, regulations and acts of India to which the Department might be subjected to.

  
Executive Engineer,  
Directorate of Textiles (Sericulture),  
West Bengal