

## Government Tender Notice.

### Invitation of Tender Notice No. 1 /Seri/Eng/Civil/RKVY/Jhargram/2020-21 ( 2<sup>nd</sup> Call )

Sealed Tenders are invited by the Executive Engineer, Sericulture, West Bengal, 45, Ganesh Chandra Avenue, (2<sup>nd</sup> floor), Kolkata-13 for the following works in the district of Jhargram under R.K.V.Y. from the bonafide experienced and resourceful contractors having experienced in such type of works in pure Govt. Department/Zilla Parishad.

| NIT | Name of the Work   | Estimated Cost   | Earnest Money  | Place of Work.                                     | Time of completion of work.                         |
|-----|--|--|--|--|---|
| 1   | Sinking of 200 mm x 150 mm dia Tube well with 1 HP Submersible pump and motor at Neguria Tasar Project Centre, Banspahari, Jhargram under R.K.V.Y. | Rs. 4,99,263.00<br>(Rupees Four lakh ninety nine thousand two hundred sixty three) only. | Rs. 12,485.00<br>(Rupees Twelve thousand four hundred eighty five) only. | Neguria Tasar Project Centre, Banspahari, Jhargram | 1 (One) month from the date of issue of Work Order. |

Tender papers (NIT), Priced Schedule & Form-2911(ii) etc. may be obtained/downloaded from [seriwb.gov.org](http://seriwb.gov.org) at free of cost.

|  |  |
|--|--|
| Last date & time of submission of Tender | 18.01.2021 upto 3-00 P.M. at Head Quarters, Kolkata. |
| Date & time of opening of Tender         | 18.01.2021 upto 3-30 P.M. at Head Quarters, Kolkata. |

Tender should be submitted/dropped in the box kept at Head Quarters, Kolkata and papers should be arranged in the following manner.

**Envelop - I**, should be superscribed as Technical Bid for N.I.T No.....SL No. of Work, Name of agency and it should contain (Self Attested) PAN Card. Last I.T. Return, valid GSTIN Registration, P.Tax Challan, Credential (similar nature of work at about 60% of Tender Value) EMD etc. and sealed.

**Envelop - II**, should be super scribed as Financial Bid for N.I.T. No..... SL No. of Work, Name of Agency and should contain filled in - **2911 (ii)** quoting the Rate and Sealed.

**2(two)** envelopes as noted above (I & II) should be put in a bigger envelop and sealed. Agency should write clearly N.I.T. No., Name of Work, SL.No. and Name of Agency on this Envelope and drop the same as per schedule mentioned in this N.I.T.

Technical Bid will be opened first. Financial Bid will be opened only if the technical Bid is found acceptable.

Labour cess will be deducted from bill value as per Govt. Rules. All original copies are to be shown for verification. The details may be seen in the Office of the **Commissioner of Textiles(Sericulture), West Bengal**, 45, Ganesh Ch, Avenue (2nd floor), Kolkata-13 on any working days and web site [seriwb.gov.org](http://seriwb.gov.org). The **Commissioner of Textiles(Sericulture), West Bengal** reserves the right to reject/cancel all the applications without showing any reasons thereof. If any date as above happens to be holidays the next working days will be considered as stipulated date. Acceptance of lowest tender is not obligatory.

N.S.C./K.V.P. will not be accepted as Earnest Money. Only the Bank Draft of a Nationalized Bank will be considered as Earnest money. Acceptance of lowest Tender is not obligatory. Notwithstanding anytime contained in this Notice Inviting Tender, the other terms & conditions and special terms & conditions will remain binding upon all concerned.

*31/1/2021*  
Executive Engineer,  
Directorate of Sericulture,  
West Bengal.

Memo. No. 369 /Seri/Eng/Civil/RKVY/MID/1 (Vol.-II),

Dated, 04/01/2021

Copy forwarded for information & necessary action to :-

1. The Deputy Director of Sericulture, Midnapur
2. The Notice Board of this Directorate.
3. The Website of this Directorate.

*31/1/2021*  
Executive Engineer,  
Directorate of Sericulture,  
West Bengal.



riced schedule for the Sinking of 200 mm x 150 mm dia Tube well at Neguria Tasar Project Centre, Banspahari, Paschim Midnapur.under RKVY.


| Sl. No. | Description of Item  | Unit     | Rate     | Quantity | Amount    |
|---------|--|----------|----------|----------|-----------|
| 1       | Labour for boring through hard rock drilling and lowering of bore hole by DTH through hard rock by rock roller bit upto 150 m depth including hire and labour charges for DTH machine, staging, lowering pipes etc. and all accessories , fuels etc. complete. For 150 mm dia Tube well with top enlargement 200 mm dia. | M        | 2000.00  | 145.00   | 290000.00 |
| 2       | Supply of PVC pipes & fittings Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). 200 mm dia. ( Casing pipe.   | M        | 2134.00  | 30.00    | 64020.00  |
| 3       | ii) 40 mm dia pipe ( Column pipe )   | M        | 207.00   | 29.00    | 6003.00   |
| 4       | Supply of G.I. bend. 40 mm dia   | Each     | 214.00   | 1.00     | 214.00    |
| 5       | Supplying fitting and fixing 1 H.P Submersible pump motor  | Each     | 16000.00 | 1.00     | 16000.00  |
| 6       | Cable for Main line to Main Switch   | M        | 104.00   | 15.00    | 1560.00   |
| 7       | Cable for Pump to main switch. 2.5 sq.mm   | M        | 96.00    | 50.00    | 4800.00   |
| 8       | Main Switch SPM 16 AMP   | Each     | 2000.00  | 1.00     | 2000.00   |
| 9       | Panel Box containing Starter   | Each     | 2500.00  | 1.00     | 2500.00   |
| 10      | Supplying, fitting and fixing check valve (horizontal) G.M. tested to 21 kg per sq. cm.  | Each     | 1480.00  | 1.00     | 1480.00   |
| 11      | Washing and developing tube well with air compressor pump and engine for 8 (eight) hours continuous pumping per day with necessary arrangements for testing the yield in gallons per hour with 'V' notch including hire and labour charges for all tools and plants and scaffolding                                      | Each Day | 7538.00  | 2.00     | 15076.00  |
| 12      | Collecting sample of water for bacteriological and chemical test from any depth at any time during execution of work including hire and labour charges for tools and plants and sterilising the equipments, paying all charges and fees, testing etc. complete in all respect as per direction.                          | Each     | 1231.00  | 1.00     | 1231.00   |
| 13      | Supplying, fitting and fixing 300 mm M.S. housing clamp of approved quality.   | Each     | 2235.00  | 1.00     | 2235.00   |
| 14      | Supply of G.I. reducing socket with I.S.I. mark. 40 mm x 20 mm.  | Each     | 66.00    | 1.00     | 66.00     |
| 14      | Supplying, fitting and fixing gunmetal wheel valve of approved brand and make tested to 21 kg per sq. cm. (for water lines only). 20 mm dia  | Each     | 604.00   | 2.00     | 1208.00   |

5/11/3/2020

|    |  |       |         |       |           |
|----|--|-------|---------|-------|-----------|
| 15 | Supplying fitting and fixing Steel wire with PVC coated  | M     | 124.00  | 35.00 | 4340.00   |
| 16 | Supplying, fitting and fixing PVC pipes of approved make of Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, long screw, reducing socket, reducing tee, 20 mm dia above ground. | M     | 177.00  | 25.00 | 4425.00   |
| 17 | -- do -- 15 mm dia   | M     | 101.00  | 20.00 | 2020.00   |
| 18 | Supplying P.V.C. water storage tank of approved quality with closed top with lid (Black) - Multilayer 500 ltrs.  | Each  | 2584.00 | 1.00  | 2584.00   |
| 19 | Supplying, fitting and fixing Chromium plated Bib Cock short body (Equivalent to Code No. 511 & Model - Tropical / Sumthing Special of ESSCO or similar brand). 15 mm dia  | Each  | 539.00  | 2.00  | 1078.00   |
| 20 | Chromium plated Stop Cock (Equivalent to Code No. 513(A) & 513(B) & Model - Tropical / Sumthing Special of ESSCO or similar 15 mm dia  | Each  | 493.00  | 2.00  | 986.00    |
| 22 | Doing Resistivity test of Soil/ rock Strata for determine underground water strata.  | Point | 6000.00 | 3.00  | 18000.00  |
|    |  |       |         |       | 441826.00 |
|    | Add. 12 % as G S T   |       |         |       | 53019.00  |
|    | Add. 1 % as Labour Welfare Cess  |       |         |       | 4418.00   |
|    |  |       | Total   |       | 499263.00 |

Rs. 4,99,263.00

( Rupees Four lakhs ninety nine thousand two hundred sixty three.

  
 11/3/2020  
 Executive Engineer  
 Directorate of Textiles (Sericulture)  
 Government of West Bengal