

## Government Tender Notice

Invitation of Tender Notice Nos. **111,113/Seri/Eng/Elec/PCR/MID(West)/2019-'20.**

Sealed Tenders are invited by the Executive Engineer, Sericulture, West Bengal, 45, Ganesh Chandra Avenue, (2<sup>nd</sup> floor), Kolkata-13 for the following Electrical works in the district of Midnapur (West) from the bonafide experienced and resourceful contractors having experienced in such type of works in pure Govt. Department / Zilla Parishad.

NIT	Name of the Work	Estimated Cost	Earnest Money	Place of Work.	Time of completion
111	Damaged electrical wiring and newly installed Incubation machine at 1 <sup>st</sup> Floor including arrangement of lightening in compound at Debra Sericulture Farm, Midnapur (West) under PCR.	<b>Rs. 2,12,329.00</b> (Rupees Two lakh twelve thousand three hundred twenty nine)only	<b>Rs. 5308.00</b> (Rupees five thousand three hundred eight) only.	Debra Sericulture Farm, Midnapur (West)	1 (One) month from the date of issue of Work Order.
113	Repairing of electrical works at DPAP farm, Jhargram, Midnapur (West) under PCR..	<b>Rs. 1,77,801.00</b> (Rupees one lakh seventy seven thousand eight hundred one)only.	<b>Rs. 4445.00</b> (Rupees four thousand four hundred forty five) Only	DPAP farm, Jhargram, Midnapur (West) under PCR..	

Tender papers (NIT), Priced Schedule & Form-2911(ii) etc. may be obtained/downloaded from [seriwb.gov.org](http://seriwb.gov.org) at free of cost.

Last date & time of submission of Tender	12.02.2020 upto 3-00 P.M. at Head Quarters, Kolkata.
Date & time of opening of Tender	12.02.2020 upto 3-30 P.M. at Head Quarters, Kolkata.

Tender should be submitted / dropped in the box kept at Head Quarters, Kolkata and papers should be arranged in the following manner.

**Envelop - I**, should be superscribed as Technical Bid for N.I.T No.....SL No. of Work, Name of agency and it should contain (Self Attested) PAN Card. Last I.T. Return, valid GSTIN Registration, P.Tax Challan, Credential (similar nature of work at about 60% of Tender Value) EMD, Electrical and Supervisor License etc. and sealed.

**Envelop - II**, should be super scribed as Financial Bid for N.I.T. No..... SL No. of Work, Name of Agency and should contain filled in - 2911 (ii) quoting the Rate and Sealed.

**2(two)** envelopes as noted above (I & II) should be put in a bigger envelop and sealed. Agency should write clearly N.I.T. No., Name of Work, SL.No. and Name of the Agency on this Envelope and drop the same as per schedule mentioned in this N.I.T.

Technical Bid will be opened first. Financial Bid will be opened only if the technical Bid is found acceptable.

Labour Cess will be deducted from bill value as per Govt. Rules. All original copies are to be shown for verification. The details may be seen in the Office of the **Commissioner of Textiles (Sericulture), West Bengal**, 45, Ganesh Ch, Avenue (2nd floor), Kolkata-13 on any working days and web site [seriwb.gov.org](http://seriwb.gov.org). The **Commissioner of Textiles (Sericulture), West Bengal** reserves the right to reject/cancel all the applications without showing any reasons thereof. If any date as above happens to be holidays the next working days will be considered as stipulated date. Acceptance of lowest tender is not obligatory.

N.S.C./ K.V.P. will not be accepted as Earnest Money. Only the Bank Draft of a Nationalised Bank will be considered as Earnest money. Acceptance of lowest Tender is not obligatory.

Notwithstanding anytime contained in this Notice Inviting Tender, the other terms & conditions and special terms & conditions will remain binding upon all concerned.

*26/12/19*  
Executive Engineer,  
Directorate of Sericulture,  
West Bengal.

Proposed schedule for Repairing and electrical work at Jhargram DPAP farm Jhargram  
, Midnapore under PCR.

<u>Srl no.</u>	<u>Description of item</u>	<u>Unit</u>	<u>Qty</u>	<u>Rate</u>	<u>Amount</u>
1	Distribution wiring in 1.1 kV grade 2x22/0.3 (1.5 sq.mm.) single core stranded "FR" PVC insulated & unsheathed copper wire (Approved make) in 20mm PVC rigid conduit FR (Precision make) with 1.1KV grade 1x22/0.5 (1.5 sq.mm.) for ECC including fittings to light/fan/call bell point with modular type switch fixing on modular type sheet steel (16SWG) switch board cum JB on wall complete with 2 nos suitable size PH & N copper bar with Perpex top cover 3mm thick incl. 175mmx100mmx65mm Inspection box making earthing attachment as to G.S. (6mt. Average long). {PED 2017/Page-E-24/SI no. 1(b)}	Points	15	801.00	12015.00
2	S/F 250V amp modular type plug socket with switch (Anchor) without top in existing switch board incl. connection & as per P.W.D. schedule . {PWD 2017/Page-E-24/sI no. 1(b)}	Points	4	216.00	864.00
3	Wiring in 1.1 Kv grade 2x36/0.3(2.5 sq.mm.) single core stranded "FR" PVC insulated & unsheathed copper wire (Approved make) with 1.1 KV grade 1x36/0.3(2.5 sq.mm.) single core stranded "FR" PVC insulated & unsheathed copper wire (Approved make) in 20mm size rigid conduit "FR" (precision) incl. necessary fitting for main line & poutdoor light. {PWD 2017/Pge-E-14/SI no. 1(a)}	Mtr	55	119.00	6545.00
4	S/F Industrial plug & socket board with 240 V , 20 A , SPN & Earth Metal Industrial plug & socket & 20A Industrial	Each	6	904.00	5424.00
5	Wiring in 1.1 Kv grade 2x56/0.3(4 sq.mm.) single core stranded "FR" PVC insulated & unsheathed copper wire (Approved make) with 1.1 KV grade 1x36/0.3(2.5 sq.mm.) single core stranded "FR" PVC insulated & unsheathed copper wire (Approved make)as ECC insuitable size PVC casing-capping (precision) incl necessary fitting to power plug & AC point. {PWD 2017/Pge-E-11/SI no. 1(e)}	Mtr	50	132.00	6600.00
6	S/F socket type fan regulator (step type) & as per instruction of EIC. {PWD 2017/Page -E-6/SI no. 11(b)}	Nos	8	236.00	1888.00

	Mirolta slim batten 36W Hf with suitable for single TMS220/136 lamp with reflector (rate analysis attached)	Nos	12	843.00	10116.00
8	S/F 1 poles 15 amp MCB with sheet steel enclosure of Havells make. {PWD 2017/Page-D-6/sl no. 7 & D-9/sl no. 11}	Nos	1	164.00	164.00
9	S/F outdoor type new generation energy saving & environment friendly long life versatile pressure die cast aluminium IP65 roadway luminaire with high power LED as light CROMPTON Make with lamp 45W. (Rate analysis attached)	Nos	20	4351.00	87020.00
10	S/ laying 2 core 10 sq.mm. PVC cable embedded in wall as per PWD schedule incl. 2x10 SWG GI earth wire. (Rate analysis attached)	Mtr	90	195.90	17631.00
11	Earthing by 2" dia x 10' 0" G.I pipe as per PWD schedule.	Each	2	1369.00	2738.00
10	Cabin Fan 16" dia USHA MAKE Supplying, fitting and fixing complete. ( Ground floor, Office.)	Each	1	2272.00	2272.00
					<b>153277.00</b>
	Add : District Charge @3%				4598.31
					157875.31
	Add : GST @12%				18393.24
	Add : CESS @1%				1533.00
	Grand Total				<b>177801.00</b>
	( Rupees one lakh seventy seven thousand eight hundred one ) only.				

  
 Executive Engineer  
 Directorate of Textiles (Sericulture)  
 Government of West Bengal