

Government Tender Notice

Invitation of Tender Notice Nos.119,121,122,123,124/Seri/Eng/Civil/PCR/BNK/2019-'20.

Sealed Tenders are invited by the Executive Engineer, Sericulture, West Bengal, 45, Ganesh Chandra Avenue, (2nd floor),Kolkata-13 for the following works in the district of Bankura from the bonafide experienced and resourceful contractors having experienced in such type of works in pure Govt. Department / Zilla Parishad.

NIT	Name of the Work	Estimated Cost	Earnest Money	Place of Work.	Time of completion of work.
119	Repairing of A.C sheet roof of Rearing house (Used by CSB) at Taldangra Tasar Farm, Bankura, under PCR.	Rs.4,71,135.00 (Rupees Four lakh Seventy one thousand one hundred Thirty five) only.	Rs. 11,780.00 (Rupees Eleven thousand Seven hundred Eighty) only.	Taldangra Bankura	1 (One) month from the date of issue of Work Order.
121	Construction of boundary wall (Front portion and Calvert, drainage system at Khatra Cocoon market, Khatra, Bankura under PCR.	Rs. 2,61,169.00 (Rupees Two lakh Sixty one thousand one Hundred Sixty nine) only.	Rs. 6530.00 (Rupees Six thousand Five hundred Thirty)Only	Khatra Cocoon market, Khatra, Bankura	-do-
122	Replacement of 5 Hp Submersible pump & Motor with change of PVC pipe line for drinking water for Office and staff Qtrs at Bishnupur Sericulture Complex, Bankura under P.C.R.	Rs. 2,29,046.00 (Rupees Two lakh Twenty nine thousand Forty six)only	Rs. 5730.00 (Rupees Five thousand Seven hundred Thirty) Only.	Bishnupur Sericulture Complex, Bankura	-do-
123	Addition and alteration of Grainage building for set up of Walk In Cold room at Bishnupur Sericulture Complex, Bankura under P.C.R.	Rs. 72,898.00 (Rupees Seventy two thousand Eight hundred Ninety eight)only.	Rs.1825.00 (Rupees One thousand Eight hundred twenty five)only.	Bishnupur Sericulture Complex, Bankura	-do-
124	Antitermite treatment for office building and Gr.'D' Qtrs (4in 1) Office campus of Deputy Director of Sericulture, Bankura under P.C.R.	Rs. 90,372.00 (Rupees Ninety thousand Three hundred Seventy two)only.	Rs. 2260.00 (Rupees Two thousand two hundred Sixty) Only.	Office campus of Deputy Director of Sericulture, Bankura	-do-

Tender papers (NIT), Priced Schedule & Form-2911(ii) etc. may be obtained/downloaded from seriwb.gov.org at free of cost.

Last date & time of submission of Tender	06.02.2020 upto 3-00 P.M. at Head Quarters, Kolkata.
Date & time of opening of Tender	06.02.2020 upto 3-30 P.M. at Head Quarters, Kolkata.

Tender should be submitted / dropped in the box kept at Head Quarters, Kolkata and papers should be arranged in the following manner.

119, 121, 122, 123, 124

Envelop - I, should be superscribed as Technical Bid for N.I.T No.....SL No. of Work, Name of agency and it should contain (Self Attested) PAN Card. Last I.T. Return, valid GSTIN Registration, P.Tax Challan, Credential (similar nature of work at about 60% of Tender Value) EMD & Pest Control License etc for NIT No.124 and sealed.

Envelop - II, should be super scribed as Financial Bid for N.I.T. No..... SL No. of Work, Name of Agency and should contain filled in - **2911 (ii)** quoting the Rate and Sealed.


2(two) envelopes as noted above (I & II) should be put in a bigger envelop and sealed. Agency should write clearly N.I.T. No., Name of Work, SL.No. and Name of the Agency on this Envelope and drop the same as per schedule mentioned in this N.I.T.

Technical Bid will be opened first. Financial Bid will be opened only if the technical Bid is found acceptable.

Labour Cess will be deducted from bill value as per Govt. Rules. All original copies are to be shown for verification. The details may be seen in the Office of the **Commissioner of Textiles (Sericulture), West Bengal**, 45, Ganesh Ch, Avenue (2nd floor),Kolkata-13 on any working days and web site seriwb.gov.org. The **Commissioner of Textiles (Sericulture), West Bengal** reserves the right to reject/cancel all the applications without showing any reasons thereof. If any date as above happens to be holidays the next working days will be considered as stipulated date. Acceptance of lowest tender is not obligatory.

N.S.C./ K.V.P. will not be accepted as Earnest Money. Only the Bank Draft of a Nationalised Bank will be considered as Earnest money. Acceptance of lowest Tender is not obligatory.

Notwithstanding anytime contained in this Notice Inviting Tender, the other terms & conditions and special terms & conditions will remain binding upon all concerned.



Executive Engineer,
Directorate of Sericulture,
West Bengal.

Memo. No. 816(3)/Seri/Eng/Civil/PCR/BNK/6(Vol.-7).

Dated, 23/12/19 2019.

Copy forwarded for information & necessary action to :-

1. The Deputy Director of Sericulture, Bankura.
2. The Notice Board of this Directorate.
3. The Website of this Directorate.


Executive Engineer,
Directorate of Sericulture,
West Bengal.

Priced schedule for Repairing of Asbestos sheet roof Rearing house (used by CSB) at Taldangra Tasar farm, Bankura under PCR.

Sl. No.	Description of work	Unit	Quantity	Rate	Amount
1	Taking out carefully Ranigunge pattern tiles from roof stacking serviceable tiles at site and removing rubbish as directed within a lead of 75m.	Sqm	100.00	62.00	6200.00
2	Dismantling carefully wood work in posts, postplates, rafters, partition etc., sorting and stacking serviceable materials at site and removing rubbish as directed.	Cum	0.75	278.00	209.00
3	Dismantling artificial stone flooring upto 50 mm. thick by carefully chiselling without damaging the base and removing rubbish as directed within a lead of 75 m.	Sqm	140.00	50.00	7000.00
4	Dismantling all types of masonry excepting cement concrete plain or reinforced, stacking serviceable materials at site and removing rubbish as directed within a lead of 75 m.	Cum	2.10	447.00	939.00
5	Labour for taking out door and window frame including shutter for repair or replacement of different parts of the frame & refixing the same including mending good all damages complete. (Concrete and brick work for mending damage will be paid separately)	Sqm	9.00	119.00	1071.00
6	Stripping off worn out plaster and raking out joints of walls, ceilings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed.	Sqm	100.00	19.00	1900.00
7	Brick work in cement mortar (1:4) in foundation and plinth.	Cum	1.20	4742.00	5690.00
8	Brick work in cement mortar (1:4) in Superstructure, Ground floor.	Cum	1.20	4965.00	5958.00
9	Wood work in posts, post plates, rafters, battens, truss members, purlins etc. fitted and fixed complete (excluding the cost of bolts, paints, but including the cost of nails, screws etc.) (The quantum should be corrected upto three decimals)	Cum	1.00	73019.00	73019.00
10	Asbestos corrugated (Trafford or similar approved quality) sheet (6 mm thick) work (excluding the supporting framework) fitted and fixed with 9.5mm. dia. J or L hook-bolt and nuts, limpet and bitumen washers and putty with 150 mm end lap & one corrugation minimum side lap complete. (Payment should be made on area of finished work)	Sqm	105.00	471.00	49455.00
11	Supplying, fitting and fixing W.P.C (Marbonate) Door and window frame 4" x 2" size (woods plastic composite)	M	30.50	1070.26	32643.00
12	Supplying fitting and fixing Vernished Moulded Panel door 32 mm thick made with approved materials as per specification of manufacturers. (MARBON)	Sqm	8.00	4834.46	38676.00
13	Artificial stone in floor, dado, staircase etc with cement concrete (1:2:4) with stone chips, laid in panels as directed with topping made with ordinary or white cement (as necessary) and marble dust in proportion (1:2) including smooth finishing and rounding off corners including raking out joints or roughening of concrete surface	Sqm	140.00	314.00	43960.00

	Supplying Fitting and fixing Steel Fly proof net with new beads where necessary.256 mesh per sq. inch. 22 gauge.	Sqm	9.00	1272.00	11448.00
15	Cement concrete with graded stone chips excluding shuttering and re reinforcement if any with (1:2:4) proportion.	Cum	6.00	5237.40	31424.00
16	Plaster to wall floor ceiling etc. with sand and cement mortar (1:4), 20 mm thick, In Ground Floor	Sqm	45.00	170.00	7650.00
17	Plaster to wall floor ceiling etc. with sand and cement mortar (1:4), 15mm thick, In Ground Floor	Sqm	110.00	149.00	16390.00
18	Neat cement punning in wall, dadoetc.	Sqm	45.00	34.00	1530.00
19	Ceiling of commercial ply as per design fitted and fixed complete (excluding the supporting framework but including necessary wood battens of size 40mm x 20mm). 6 mm thick Local Sal wood	Sqm	56.00	712.00	39872.00
20	Iron butt hinges of approved quality fitted and fixed with steel screws, with ISI mark.vi) 75 mm. X 47 mm. X 1.70mm.	Each	24.00	31.00	744.00
21	Iron butt hinges of approved quality fitted and fixed with steel screws, with ISI mark.vi) 100mm. X 50mm. X 1.25mm.	Each	6.00	47.00	282.00
22	Iron hasp bolt of approved quality fitted and fixed complete (oxidised) with 16mm dia rod 300 mm long	Each	1.00	166.00	166.00
23	Iron socket bolt fitted and fixed complete. 150 mm long.	Each	16.00	63.00	1008.00
24	White washing including cleaning and smoothening surface thoroughly. 2 coats.	Sqm	100.00	18.14	1814.00
25	Applying Exterior grade Acrylic primer of approved quality and brand on plastered or concrete surface old or new surface. In Ground Floor.	Sqm	165.00	45.10	7442.00
26	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction. In Ground Floor	Sqm	165.00	84.00	13860.00
27	Priming one coat on timber or plastered surface with synthetic oil bound primer	Sqm	56.00	38.00	2128.00
28	Painting with best quality synthetic enamel paint of approved make and brand On timber or plastered surface :	Sqm	56.00	81.00	4536.00
29	Supplying, fitting and fixing G.C.I corner Ridge on Verandah roof.	m	11.00	380.00	4180.00
30	Repairing of M.S.or W.I. Ornamental grill of approved design joints continuously welded with M.S, W.I. Flats and bars of windows, railing etc. fitted and fixed with necessary screws and lugs in ground floor.	Kg	50.00	72.38	3619.00
31	Painting with ready mixed Black Japan of approved make and brand including smoothening surface. 2 coats.	Sqm	30.00	56.00	1680.00
					416493.00
					Add. 12 % as GST
					49979.00
					Add. 1 % as Labour Welfare Cess.
					4663.00
					Total
					471135.00

Rs. 4,71,135.00

(Rupees Four Lakhs Seventy one thousand one hundred thirty five only).


Executive Engineer
Directorate of Textiles (Sarculture)
Government of West Bengal