

Government Tender Notice

Invitation of Tender Notice Nos. 99,101/Seri/Eng/Elec/PCR/Nadia2019-'20.

Sealed Tenders are invited by the Executive Engineer, Sericulture, West Bengal, 45, Ganesh Chandra Avenue, (2nd floor), Kolkata-13 for the following Electrical works in the district of Nadia from the bonafide experienced and resourceful contractors having experienced in such type of works in pure Govt. Department / Zilla Parishad.

NIT	Name of the Work	Estimated Cost	Earnest Money	Place of Work.	Time of completion
99	Internal electrical works of newly repaired Qtrs. (1 unit), renewing different fittings, at Rearing house , Office, and compound light at Ranaghat Sericulture Complex, Ranaghat, Nadia under PCR.	Rs. 1,91,333.00 (Rupees one lakh ninety one thousand three hundred thirty three)only	Rs. 4785.00 (Rupees four thousand seven hundred eighty five) only.	Ranaghat Sericulture Complex, Ranaghat, Nadia	1 (One) month from the date of issue of Work Order.
101	Replacement work of damaged street light by new generation LED at Karimpore Sericulture Farm, Nadia under PCR.	Rs. 98,288.00 (Rupees one lakh seventy seven thousand eight hundred one)only.	Rs. 2460.00 (Rupees two thousand four hundred and sixty) Only	Karimpore Sericulture Farm, Nadia	

Tender papers (NIT), Priced Schedule & Form-2911(ii) etc. may be obtained/downloaded from seriwb.gov.org at free of cost.

Last date & time of submission of Tender	10.02.2020 upto 3-00 P.M. at Head Quarters, Kolkata.
Date & time of opening of Tender	10.02.2020 upto 3-30 P.M. at Head Quarters, Kolkata.

Tender should be submitted / dropped in the box kept at Head Quarters, Kolkata and papers should be arranged in the following manner.

Envelop - I, should be superscribed as Technical Bid for N.I.T No.....SL No. of Work, Name of agency and it should contain (Self Attested) PAN Card. Last I.T. Return, valid GSTIN Registration, P.Tax Challian, Credential (similar nature of work at about 60% of Tender Value) EMD, Electrical and Supervisory License etc. and sealed.

Envelop - II, should be super scribed as Financial Bid for N.I.T. No..... SL No. of Work, Name of Agency and should contain filled in - **2911 (ii)** quoting the Rate and Sealed.


2(two) envelopes as noted above (I & II) should be put in a bigger envelop and sealed. Agency should write clearly N.I.T. No., Name of Work, SL.No. and Name of the Agency on this Envelope and drop the same as per schedule mentioned in this N.I.T.

Technical Bid will be opened first. Financial Bid will be opened only if the technical Bid is found acceptable.

Labour Cess will be deducted from bill value as per Govt. Rules. All original copies are to be shown for verification. The details may be seen in the Office of the **Commissioner of Textiles (Sericulture), West Bengal**, 45, Ganesh Ch, Avenue (2nd floor),Kolkata-13 on any working days and web site seriwb.gov.org. The **Commissioner of Textiles (Sericulture), West Bengal** reserves the right to reject/cancel all the applications without showing any reasons thereof. If any date as above happens to be holidays the next working days will be considered as stipulated date. Acceptance of lowest tender is not obligatory.

N.S.C./ K.V.P. will not be accepted as Earnest Money. Only the Bank Draft of a Nationalised Bank will be considered as Earnest money. Acceptance of lowest Tender is not obligatory.

Notwithstanding anytime contained in this Notice Inviting Tender, the other terms & conditions and special terms & conditions will remain binding upon all concerned.



Executive Engineer,
Directorate of Sericulture,
West Bengal.

Memo. No. 832(3)/Seri/Eng/Elec/PCR/NAD/3(Vol.- 5),

Dated, 26/12 2019.

Copy forwarded for information & necessary action to :-

1. The Deputy Director of Sericulture, Krishnagar, Nadia.
2. The Notice Board of this Directorate at Head Qtrs., Kolkata.
3. The Website of this Directorate.


Executive Engineer,
Directorate of Sericulture,
West Bengal.

Priced Schedule for internal electrical work of newly repaired Qtr. (1 unit), renewing different fittings at R.H. office and compound light at Ranaghat Sericulture Complex, Ranaghat, Nadia, under P.C.R.2019-20.

Sl.No	Description of item	Unit	Qty.	Rate (Rs.)	Amount(Rs.)
01.	S/F of 9 W LED lamp of Philips make Office -12, For three nos R.H -18	Each	30	100.00	3000.00
02.	Supplying fitting and fixing Miroлта slim batten 36 W HP (Phillips make) with suitable for single TMS 520/136 with lamp of 1200 mm long.(for 3 RH).	Each	10	843.00	8430.00
03.	Supplying of 1200 mm long slim pattern batten lamp 20 watt smart bright vide model no.- BNO21LED20SPSUCWGRS2 of Philips fitted and fixing complete as per PWD schedule of rate .(Analysis rate.) (for office -8, new SHG room- 3, grainage -3)	Each	14	Rs.1035.00	14,490.00
04.	S/F outdoor type new generation energy saving & environment friendly long life versatile pressure die-cast aluminium IP65 roadway luminaries with high power LED as light CROMPTON Make with lamp type 40W LSTS-40-CDL(FREEDOM)	Each	16	4723.00	75568.00
05.	S/F outdoor type new generation energy saving & environment friendly long life versatile pressure die-cast aluminium IP65 roadway luminaries with high power LED as light CROMPTON Make with lamp type 72W LSTP-72-CDL(NEXUS).	Each	02	8793.00	17,586.00
06.	Supplying fitting and fixing Industrial plug & socket board with 240 V, 20A, SPN & Earth Metal etc. And necessary connection.(for R.H)	Each	04	904.00	3616.00
07.	Supplying fitting and fixing 9 inch dia Exhaust fan (CROMPTON Make) single phase incl. Shutter and cover making hole on wall and mending good damages to wall. (SHG room-1)	Each	01	2171.00	2171.00
08.	Supplying fitting and fixing 48 inch dia ceiling fan (CROMPTON Make) with regulator (Entrust-50,5 star)	Each	02	2213.00	4426.00
09.	Wiring in 1.1 KV grade 2x36/0.3 (2.5sq.mm.) single core sheathed FR PVC insulated & unsheathed single core standard copper wire (Aproved Make) with 1.14 KV grade 1x36/0.3 (2.5sq.mm.) single core standard FR PVC insulated & unsheathed single core standard copper wire (Approved Make) in 20mm size rigid conduit FR (precision) incl necessary fitting for main line and outdoor light.	Mtr.	40.00	136.00	5440.00
10.	Distribution wiring in 1.1 KV grade 2x22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) in suitable size PVC casing-capping (Precision make) with 1x22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire for ECC, incl. necy. PVC clips, fittings etc. to light/fan/call bell point with piano key type switch (Anchor make) fixed on sheet steel fabricated switch board with Perspex/ bakelite top cover on wall incl. necy. connections and making earthing attachment and mending good damages to building works. Average run 6 mtr.	Point	10	650.00	6550.00

11.	Earthing with 50 mm dia GI pipe 3.64 mm thick x 3.04 Mts.long and 1 x 4 SWG GI (Hot Dip) wire (4 Mts. long), 13 mm dia x 80 mm long GI bolts, double nuts, double washers incl. S & F 15 mm dia GI pipe protection (1 Mts. long) to be filled with bitumen partly under the ground level and partly above ground level driven to an average depth of 3.65 Mts. below the ground level as below: (a) By ISI-Medium GI pipe	Each	01	1,369.00	1369.00
12.	Supplying /Laying 2-core 6 sq.mm PVC/A cable partly in the underground trench as PWD schedule & partly embedded in wall as PWD schedule from overhead line (PWD schedule 2017,Page-F2,Sl.No.-1(a).	Mtr.	30	285.86	8576.00
13.	Supplying fitting and fixing 32 mm dia protection pipe as per PWD schedule.	Mtr.	6.00	218.00	1308.00
14.	Painting of Steel Tubular Pole of lengths and no. of coats of paint, as given below with ready mixed paint/primer of approved make, and brand incl. preparation of surface by sand paper/emery paper, cleaning etc. for receiving fresh coat of paint. a) Up to 9 mtr. Pole height. i) 1 st coat of aluminium paint over 1 coat of RO priming per pole Rs. 226.00 (ii) 2 nd coat of aluminium paint over 1 st coat per pole Rs. 103.00 (Total=329.00per pole)	Each	25	329.00	8225.00
15.	Repairing of existing tubular pole at bottom part by m.s. sheet after dismantling of muffing.	Each	01	2500.00	2500.00
16.	Providing CC (6:3:1) muffing 600x600x760 mm in size or equivalent size of cylindrical muffing above ground level around the pole base complete with 3 mm thick neatly finished cement plaster all round after dismantling the unserviceable muffing if Necessary. a) Without Loop Box	Each	01	1134.00	1134.00

Total= Rs. 1, 64,389.00
Add. 3 % as District Charge _____ Rs. 4932.00
Rs. 1, 69,321.00
Add. 12 % as GST _____ Rs. 20,319.00
Labour welfare cess @1% _____ Rs. 1,693.00
Total = Rs. 1, 91,333.00

of 23/11/15
Executive Engineer
Directorate of Textiles (Sericulture)
Government of West Bengal