

**Government Tender Notice**

Invitation of Tender Notice No.31,33 & 35/Seri/Engg/Civil/PCR/UD/2017-'18. ( 2nd Call )

Sealed Tenders are invited by the Executive Engineer, Directorate of Textiles(Sericulture), West Bengal, 45, Ganesh Chandra Avenue (2nd floor),Kolkata-13 for the following works in the district of Uttar Dinajpore under P.C.R. works from the bonafide experienced and resourceful contractors having experienced in such type of works in pure Govt. Department/Zilla Parishad.


NIT No.	Name of the Work.	Estimated Cost.	Earnest Money	Last date of submission of Tender.	Date & time of opening of Tender	Place of Work.	Time for completion
31 2nd Call	Repairing of Gr.-'D' Qtrs. ( No.D-5 ) at Hemtabad Sericulture Farm, Uttar Dinajpore under P.C.R.	Rs.4,16,934/- (Rupees four lakh sixteen thousand nine hundred thirty four) only.	Rs.10,425/- (Rupees ten thousand four hundred twenty five) only.	02.01.2018 upto 3-00 P.M. at H.Q.,Kolkata	02.01.2018 at 3-30 P.M. at H.Q., Kolkata.	Hemtabad Sericulture Farm,Uttar Dinajpore.	1 (one) month
33 2nd call	Repairing of Rearing House No.1 at Fulhara Seri. Composite Unit at Islampur, Uttar Dinajpur under P.C.R.	Rs.4,99,915/- (Rupees four lakh ninety nine thousand nine hundred fifteen)only.	Rs.12,500/- (Rupees twelve thousand five hundred)only.	-do-	-do-	Fulhara Seri. Comp. Unit, Islampur, Uttar Dinajpur.	-do-
35 2nd call	Repairing of G.C.I. roof of Office of the Asstt. Director, Textiles, Sericulture at Bogram, Uttar Dinajpur under P.C.R.	Rs.2,87,517/- (Rupees two lakh eighty seven thousand five hundred seventeen)only	Rs.7,190/- (Rupees seven thousand one hundred ninety) only.	-do-	-do-	Office of Assistant Director, Textiles, Sericulture Bogram, U/Dinajpur.	-do-

Tender Papers (NIT, Priced Schedule & Form : 2911(ii) etc.) may be obtained/downloaded from [seriwb.gov.org](http://seriwb.gov.org) at free of cost. Tender papers should be submitted in the Box kept at Head Quarters, Kolkata and papers should be arranged in the following manner.

Envelope - I, should be super scribed as Technical Bid for N.I.T.No....., of work. Name of the Agency and it should contain (Self Attested) i) PAN Card. Last I.T. Return. Valid GSTIN Registration, P.T. Challan, Credential (Similar nature of work at about 60% of Tender value), Pest Control License for the works of Sl.Nos.3 & 8 respectively, E.M.D. and sealed.

Envelope - II, should be super scribed as Financial Bid for N.I.T. No....., of work, Name of Agency and should contain filed on 2911(ii) quoting the Rate and Sealed. 2(two) Envelopes as noted above (I & II) should be put in a bigger Envelope and sealed. Agency should write clearly N.I.T. No..... Name of Work, and Name of Agency on this Envelope and drop the same as per scheduled mentioned in this N.I.T.


Technical Bid will be opened first. Financial Bid will be opened only if the Technical Bid is found acceptable. Labour Cess will be deducted from Bill value as per Govt. Rules. All original copies are to be shown for verification. The details may be seen in the Office of the Commissioner of Textiles (Sericulture), West Bengal 45, Ganesh Ch. Avenue (2nd floor),Kolkata - 13 on any working days and in Website : [seriwb.gov.org](http://seriwb.gov.org). The Commissioner of Textiles (Sericulture), West Bengal reserves the right to reject/accept all the applications without showing any reasons thereof. If any date as above happens to be holiday the next working day will be considered as stipulated date. Acceptance of lowest Tender is not obligatory. N.S.C./K.V.P. will not be accepted as Earnest Money. Only the bank Draft of a Nationalized Bank will be considered.

  
 Executive Engineer,  
 Directorate of Textiles (Sericulture),  
 West Bengal.

Price schedule for repairing of Rearing House (1 No.) at Fulhara Sericulture comp.Unit, P.O.-Ramganj, Islampur in the Dist. Of Uttar Dinajpur under PCR.

01.	Dismantling RC floor beams etc including cutting rods and removing rubbish as directed.	4.50m <sup>3</sup>	1975.00/m <sup>3</sup>	8888.00
02.	Dismantling all types of terraced floor including lime terracing in G.F. roof. Stacking as directed. Within a lead of 75 m.	10m <sup>3</sup>	949.00/m <sup>3</sup>	9490.00
03.	Stripping off worn out plaster and racking out joints of wall ceiling etc. up to any height, and in any floor including removing rubbish as directed. Within a lead of 75 m.	508m <sup>2</sup>	19.00/m <sup>2</sup>	9652.00
04.	Supplying and laying polythene sheet (150 Gm/sq.m) below concrete surface.	42m <sup>2</sup>	25.00/m <sup>2</sup>	1050.00
05.	Brick work with 1 <sup>st</sup> class bricks in cement mortar (1:6) in superstructure.	1.15m <sup>3</sup>	5517.00/m <sup>3</sup>	6345.00
06.	Cement concrete with 30 mm down graded shingles excluding shuttering (1:3:6)	1.30m <sup>3</sup>	4221.00/m <sup>3</sup>	5487.00
07.	Ordinary cement concrete (Mix 1:2:4) with graded stone chips (20 mm (20mm dia) excluding shuttering and reinforcement Pakur Variety. (i) In G.F.	4.20m <sup>3</sup>	5038.00/m <sup>3</sup>	21160.00
08.	Ordinary cement concrete M-15 (mix 1:1.5:3) with graded stone chips (20 mm dia) excluding shuttering and reinforcement Pakur variety.	21m <sup>3</sup>	5920.00/m <sup>3</sup>	124320.00
09.	Hire and labour charges for shuttering with centering and necessary staging up to 4 m and thick hard wood planks of approved thickness with required bracing for concrete slab, beams etc. including fitting and fixing and striking out after completion of works.(i) with staging. (ii) Without staging.	43m <sup>2</sup> 15m <sup>2</sup>	351.00/m <sup>2</sup> 221.00/m <sup>2</sup>	15093.00 3315.00
10.	Reinforcement for reinforced concrete work in all sorts of structure including distribution bars, strups, binder etc. and removal of loose rust ( if necessary) cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection complete as per drawing as directed. Tor Steel. (i) In G.F.	2.50Qtl	6304.90/Qtl	15762.00
11.	75 mm thick brick work with 1 <sup>st</sup> class bricks etd in cement sand mortar(1:4).	4m <sup>2</sup>	505.00/m <sup>2</sup>	2020.00
12.	Labour for taking out doors and windows including shutter for repair and replacement of different parts of the frame and re fixing the same including mending good all damage complete.	20m <sup>2</sup>	121.00/m <sup>2</sup>	2420.00
13.	Dismantling artificial stone flooring up to 50 mm thick by carefully chiselling with out damaging the base and removing rubbish as directed. Within a lead of 75 m. In G.F.	34m <sup>2</sup>	50.00/m <sup>2</sup>	1700.00
14.	Wood work in doors and windows frame fitted and fixed complete including a protection coat of painting at the contact surface of the frame excluding cost of concrete Hard wood.	0.40m <sup>3</sup>	57415.00/m <sup>3</sup>	22966.00
15.	Taking out grills from wooden frame including cutting lugs and re fixing the same.	4 Nos.	100.00/each	400.00
16.	S/F/F M.S. clamp for fitting doors and windows frame made of flat ;bent bar and bifurcated with necessary screws etc. by cement concrete (1:2:4) as per direction.40mmx 6mmx250mm length.	44 Nos.	33.00/each	1452.00

Contd...(P).....(2).....

  
 Executive Engineer,  
 Directorate of Textiles (Sericulturte),  
 West Bengal

--(2)--

17.	Artificial stone floor, dado, stair case etc. with cement concrete (4:2:1) with stone chips laid in panels as directed with toppings made with ordinary cement including smooth finishing all complete including all materials and labour 3mm thick topping 35 mm thick chap.	34m <sup>2</sup>	361.00/m <sup>2</sup>	12274.00
18.	MS structural works in columns, beams etc with simple rolled structural members, angle, chanel etc. connected to one another as per design complete including welding fabrication hoisting and erection all complete for lader.	70 Kg.	69.61/Kg.	4873.00
19.	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed And racking out joints or roughening of surface including threating, nosing and drip course where necessary. (A) In G.F.: (i) Wtih (4:1) cement mortar, 19mm thickness (ii) With (6:1) cement mortar(inside), 20 mm thickness. (iii) With (6:1) cement mortar (outside), 15mm thickness.	81m <sup>2</sup> 222m <sup>2</sup> 229m <sup>2</sup>	173.00/m <sup>2</sup> 176.00/m <sup>2</sup> 152.00/m <sup>2</sup>	14013.00 39072.00 34808.00
20.	Neat cement punning about 1.5 mm thick in wall, dado window sills, floor, drain etc.	65m <sup>2</sup>	39.00/m <sup>2</sup>	2535.00
21.	M.S.or W.I ornamental grill of approved design joints continuously welded with M.S., W.I. Flats and bars of windows, railing etc. Fitted and Fixed with necessary screws and lugs. Grill weighing above 10 Kg/M <sup>2</sup> up to 16 Kg./m <sup>2</sup>	40 Kg.	83.81/Kg.	3352.00
22.	Panel shutter of doors and windows as per design including fitting and fixing the same in position but excluding the cost of hinges. 35mm thick shutter with 19 mm thick panel gamar.	6m <sup>2</sup>	3144.00/m <sup>2</sup>	18864.00
23.	Shutter 2/3 <sup>rd</sup> panel and 1/3 <sup>rd</sup> glazed of doors and windows as per design and with ordinary glass fitted with putty bed and teak wood beads and nails including fitting and fixing shutter in position. 35mm thick shutter, 19 mm thick panel.gamar.	3.80m <sup>2</sup>	3381.00/m <sup>2</sup>	12848.00
24.	Styles and rails of wooden (Payment to be made on area of new work only) 35 mm thick shutter champ.	3.50m <sup>2</sup>	2433.00/m <sup>2</sup>	8516.00
25.	Iron butt hinges of approved quality fitted and fixed with steel screws with ISI mark.(i) 75mm x 47mmx1.70mm. (ii)100mm x 58mm x 1.90mm	16 Nos. 24 Nos.	34.00/each 52.00/each	544.00 1248.00
26.	Iron socket bolt of approved quality fitted and fixed complete. 100mm long x 10 mm dia bolt.	8 Nos.	45.00/each	360.00
27.	Iron skeleton bolt of approved quality fitted and fixed complete. 375 mm long x 10 mm dia. Rod.	2 Nos.	105.00/each	210.00
28.	Iron hasp bolt of approved quality fitted and fixed completes with 16 mm dia rod with center bolt and round fitting 300mm long.	2 Nos.	193.00/each	368.00
29.	Iron catch hook of approved quality fitted and fixed to shuttering and chowkat 6mm dia x 100 mm long.	16 Nos.	40.00/each	640.00
30.	Anodized aluminium D-type handle of approved quality, fitted & fixed complete 100 mm grip x 10 mm dia.	12 Nos.	70.00/each	840.00

Conted.....(p).....(3).....—

  
Executive Engineer,  
Directorate of Textiles (Sericulturte),  
West Bengal

--(3)--

..	White washing including cleaning and smoothening surface thoroughly – 2 coats.	354m <sup>2</sup>	18.87/m <sup>2</sup>	6680.00
32.	Applying exterior grade acrylic primer of approved quality and brand on plastered surface incl. Preparing the surface one coat.	191m <sup>2</sup>	34.04/m <sup>2</sup>	6502.00
33.	Protective and decorative Acrylic exterior emulsion paint of approved quality as per manufactured specification and as per direction of the E.I.C.	191m <sup>2</sup>	108.00/m <sup>2</sup>	20628.00
34.	Priming one coat on plastered or tinber surface including smoothening surface by sand of papering etc.	31m <sup>2</sup>	41.00/m <sup>2</sup>	1271.00
35.	Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface.-2 coats if necessary.(i) On timber wood (ii) On steel	90m <sup>2</sup> 18m <sup>2</sup>	89.00/m <sup>2</sup> 86.00/m <sup>2</sup>	8010.00 1548.00
36.	S/F/F Fly/Mosquito proof steel net on any type of window, door shutter etc. with necessary fixing arrangement complete.	30.85m <sup>2</sup>	1568.00/m <sup>2</sup>	48373.00

Rs. 4,99,915.00

Executive Engineer,  
Directorate of Textiles ( Sericulture)  
West Bengal.